

PROJECT TITLE

STAG BREWERY

DRAWING TITLE

LANDSCAPE LEVEL PLAN

GILLESPIES

06.09.2017

NOT TO SCALE @ A3 DATE


SCALE

+6.30M +6.03M +5.53M GRADING SITE BOUNDARY

+7.03M

+6.70M

+6.60M



ALLUVIUM AND RIVER TERRACE DEPOSITS



© WATERMAN INFRASTRUCTURE & ENVIRONMENT



Project Details

Figure Title

Figure Ref Date File Location

WIE10667-101: Stag Brewery, Mortlake

Figure A6: Conceptual Site Model

WIE10667-101_GR_PERA_A6B 2017

\\s-Incs\wiel\projects\wie10667\101\graphics\pera\issued figures

www.watermangroup.com



Appendix B Site Photographs

• Plates 1-12

Environmental Risk Assessment Appendices

Projects/W/IE10667/101\8 Reports\4 Generic Quantitative Environmental Risk Assessment/W/IE10667-





Photograph 2. General conditions at East Site

Photograph 3. Interior of packaging warehouse



Photograph 4. General conditions at East Site



Photograph 5. General conditions at East Site

© WATERMAN INFRASTRUCTURE & ENVIRONMENT

Reproduced from the Ordnance Survey maps with the permission of the Controller of Her Majesty's Stationery Office, Crown copyright, Waterman Infrastructure & Environment, Pickfords Wharf, Clink Street, London SE1 9DG. Licence number LAN1000628.







Project Details

Figure Title

Figure Ref Date File Location WIE10667-101: Stag Brewery, Mortlake

Figure B1: Site Photograhps

WIE10667-101_GR_GERA_B1A 2017 \\s-Incs\wiel\projects\wie10667\101\graphics\gera\issued figures

www.watermangroup.com



Photograph 6. General condition of River Wall adjacent to the Site



Photograph 7. Ground investigation works in progress



Photograph 8. Typical completed borehole



Photograph 9. Follow-up groundwater monitoring works



Photograph 10. Typical completed borehole

© WATERMAN INFRASTRUCTURE & ENVIRONMENT





Project Details

Figure Title

Figure Ref Date File Location WIE10667-101: Stag Brewery, Mortlake

Figure B2: Site Photograhps

WIE10667-101_GR_GERA_B2A 2017 \\s-Incs\wiel\projects\wie10667\101\graphics\gera\issued figures

www.watermangroup.com



Appendix C Soil Consultants Geotechnical Report

• Soil Consultants - Report On Preliminary Ground Investigation: Stag Brewery, Lower Richmond Road, Mortlake, London SW14 7ET. November 2016 (*report ref. 10022/OT/JRCB*)



REPORT ON PRELIMINARY GROUND INVESTIGATION

PROPOSED REDEVELOPMENT:

STAG BREWERY, LOWER RICHMOND ROAD, MORTLAKE, LONDON SW14 7ET



Client:	RESELTON PROPERTIES LIMITED
Agent:	DARTMOUTH CAPITAL ADVISORS LIMITED
Engineers:	WATERMAN STRUCTURES LIMITED Pickfords Wharf, Clink Street London SE1 9DG
Report reference:	10022/OT/JRCB
Date:	08 November 2016 (Rev.0)

Harwich Office Haven House, Albemarle Street Harwich, Essex CO12 3HL t: 01255 241639 e: harwich@soilconsultants.co.uk

Head Office

Chiltern House, Earl Howe Road Holmer Green, High Wycombe Buckinghamshire HP15 6QT t: 01494 712 494 e: mail@soilconsultants.co.uk w: www.soilconsultants.co.uk

Registered in England No 1814762 VAT No 491 8249 15

Cardiff Office

23 Romilly Road Cardiff CF5 1FH t: 02920 403575 e: cardiff@soilconsultants.co.uk

REPORT ON PRELIMINARY GROUND INVESTIGATION

PROPOSED REDEVELOPMENT:

STAG BREWERY, LOWER RICHMOND ROAD, MORTLAKE, LONDON SW14 7ET

DOCUMENT ISSUE STATUS:

Issue	Date	Description	Author	Checked/approved
Rev 0	08 November	First issue	Opher Tolkovsky	John Bartley
	2016		BSc, MSc, DIC, CGeol, FGS	BSc, MSc, FGS, CGeol

Soil Consultants Ltd (SCL) has prepared this Report for the Client in accordance with the Terms of Appointment under which our services were performed. No other warranty, expressed or implied, is made as to the professional advice included in this Report or any other services provided by us. This Report may not be relied upon by any other party without the prior and express written agreement of SCL.



TABLE OF CONTENTS

Introduction	
Site Description	1
Previous Investigations	2
Current SCL Exploratory Work	4
Geology and Ground Conditions	6
Made ground	7
Alluvium	7
Kempton Park Gravel	7
London Clay Formation	8
Groundwater	9
Environmental observations	
Preliminary Geotechnical Assessment	10
Basement excavation and retaining wall	
Basement raft design	12
Piled foundations	12
Foundation concrete	14
Further geotechnical investigations	15
	Site Description Previous Investigations Current SCL Exploratory Work Geology and Ground Conditions Made ground Alluvium Kempton Park Gravel London Clay Formation Groundwater Environmental observations Preliminary Geotechnical Assessment Basement excavation and retaining wall Basement raft design Piled foundations Foundation concrete

General Information, Limitations and Exceptions



APPENDIX

Fieldwork, in-situ testing

- Cable percussion borehole records
- Dynamic sample borehole records
- Standard Penetration Test (SPT) results
- SPT hammer energy certificates
- Laboratory testing and monitoring
- Summary of classification test results
- Plasticity charts
- Particle size distribution results
- Summary of undrained shear strength test results
- Soluble Sulphate/pH results (QTS Environmental)

Ground model/summary plots

- SPT and c_u vs depth
- Depth to top River Terrace Deposits
- Depth to top London Clay Formation
- Schematic geological cross sections

Plans & drawings

- Architectural drawings
- Topographical survey drawings
- Site Plan
- Location Maps



1.0 INTRODUCTION

Consideration is being given to the redevelopment of the former Stag Brewery site, Mortlake, which is to be demolished and replaced with educational, commercial, retail, leisure and residential apartment blocks (3-8 storeys) with a single storey basement to provide car parking facilities and plant rooms.

The redevelopment is to be carried out in three phases. The current preliminary exploratory work was restricted to Phases 1 and 2 (east of Ship lane) and this report specifically relates to those areas. However the review of available data does include some historical information within the Phase 3 area which we also comment on for completeness.

In connection with the proposed works, Soil Consultants Ltd (SCL) were commissioned by Dartmouth Capital Advisors Ltd, on behalf of Reselton Properties Ltd (the Client) to carry out a ground investigation to include the following elements:

- Review of existing geological/geotechnical information
- Limited intrusive work (eastern part of the site only) to identify the ground sequence
- Geotechnical and contamination sampling
- Geotechnical laboratory testing
- Factual and interpretative reporting of geotechnical results

This report reviews the existing information available, describes the investigation undertaken and then provides the exploratory and field/laboratory testing records together with preliminary geotechnical recommendations. Contamination/environmental assessment is being undertaken separately by Waterman Infrastructure & Environment (WIE), who have also undertaken the Desk Study of the site.

2.0 SITE DESCRIPTION

The site is located in Mortlake in the London Borough of Richmond upon Thames and is centred at approximate National Grid reference of 520410E, 176030N. The overall site is bound to the north by River Thames, to the south by Lower Richmond Road/Mortlake High Street, to the west by Williams Lane and to the east by Bulls Alley. The overall site is divided into two by Ship Lane.

The site is a triangular-shaped plot of land which covers an area of approximately 9 hectares (22 acres). The existing site level (shown on APR Services, 'Land Survey', Drawing No. 915213-7, July 2015 - see copy in the Appendix), lies at approximately +4.5m to +6.5mOD with the highest ground to the west falling down to the east. We understand that the proposed site levels will be similar to the existing.

The site contains many disused building with the majority of the remaining areas comprising access roads, loading bays and hardstanding. The bottling plant dominates the eastern half of the site whilst the south-western corner of the site comprises a grassed sports ground. The site is almost totally devoid of vegetation with the exception of a row of large trees (Sycamore or London Plane?) along the western side of Ship Lane, and on the periphery of the sports ground.



The current proposal is to carry out the majority of the development in three phases (Phases 1 to 3) as shown below. Phases 1 and 2 comprise the eastern half of the site, east of Ship Lane and Phase 3 comprises the western half of the site.

Whilst we discuss some elements of previous investigations and historical borehole information which fall into the Phase 3 area, at this stage the exploratory work carried out for this preliminary investigation was restricted to Phases 1 and 2.



3.0 PREVIOUS INVESTIGATIONS

Three previous investigation reports (within the site) have been obtained, which are summarised below.

- 1. Soil Consultants Ltd Project Stabilise, Budweiser Stag Brewing Company Ltd, Ref. 3665/JAD/TSR, January 2004
 - This investigation comprised 3no boreholes, up to 12.5m deep located in the western site area between the sports ground and Ship Lane.
 - The boreholes proved a succession of made ground followed by localised superficial soils, River Terrace Deposits and the London Clay Formation
 - The made ground was highly variable, including soft clay, attaining a thickness of between 0.8m to 1.7m. At one location this overlay soft sandy clay with scattered gravel extending to about 2.2m depth. Generally dense sand and gravel to between about 5.5m and 6m depth was present in all boreholes. The London Clay Formation was then met, described as firm to stiff becoming stiff grey fissured clay, slightly silty in part and with local brown staining at top, which continued



to the base of the boreholes. Groundwater was recorded within the sand and gravel layer, at between 5.1m and 5.6m depth.

- 2. Ground Explorations Ltd Report on Exploration of ground conditions, Report No. 8320/RSW/vw, June 1980
 - This investigation comprised 3no boreholes, up to 15.0m deep, located in the eastern part of the site
 - The boreholes proved a succession of made ground followed by River Terrace Deposits (two boreholes) and the London Clay Formation (all three boreholes)
 - The made ground was variable, including granular and cohesive deposits, attaining a thickness of between 1.5m to 4.6m. Generally dense or very dense sand and gravel was present in two of the boreholes to about 5.5m depth. The London Clay Formation was then present, directly beneath the made ground in one borehole, comprising stiff brown fissured clay becoming stiff to very stiff grey fissured silty clay with depth. Groundwater was recorded within the boreholes at between 3.0m and 4.0m depth, with standing water level recorded at 2.6m bgl in BH2
 - The eastern side of the site is indicated in the report to contain infilled basements
- 3. AECOM Phase 2 Environmental Site Assessment Report Report Ref. 47075502, September 2015
 - o 31no shallow boreholes were drilled to a maximum depth of 6.0m
 - Where penetrated made ground was generally proven across the site to between 1.2m and 2.6m depth; buried obstructions (relict concrete slabs) were encountered at eleven locations, at a maximum depth of 3.6m in one of the boreholes (where the base of the made ground was not proven)
 - Superficial deposits were present beneath the made ground (where penetrated) comprising both soft cohesive soils, extending to a maximum of 2.6m bgl, followed by sands and gravels. The full thickness of the gravel was only recorded in one borehole at about 5m depth
 - The top of London Clay Formation was only proven in one borehole at about 5m depth. AECOM refer to an earlier investigation (2003) which investigated the western half of the site plus the south-western corner of the eastern site area, and this recorded the top of the London Clay at between 6.5m and 6.9m bgl, and at one position it was not present to the base of the BH at 7.2m depth. The report notes, however, that the use of auger drilling techniques means that the depths recorded may not be very accurate.



- Groundwater monitoring indicated water depths range between 3.57m and 5.14m bgl. A small tidal influence of 60mm was measured over a short period of 2.5 days although it is not stated whether this reflects a spring tide condition where the water range differences between low and high tide are at their highest
- 4. In addition to the above investigations, several historical BGS borehole records are also available, the most recent and detailed of which are summarised below:
 - TQ27NW/393 Cementation Ground Engineering borehole from 1972: located in the western part of the site, close to the SCL boreholes described above. Encountered made ground to 1.2m depth followed by soft to firm sandy clay to 1.5m, sand and gravel to 6.4m and stiff London Clay to the base of the borehole at 10.05m. Water strike at 6.1m
 - TQ27NW/394 Cementation Ground Engineering borehole from 1972: located in the central area of the western part of the site. Encountered made ground to 0.9m depth followed by sand and gravel to 6.85m and stiff London Clay to the base of the borehole at 20.0m. Water strike at 6.1m
 - TQ27NW/398 Cementation Ground Engineering borehole from 1972: located near Ship Lane in the western part of the site. Encountered made ground to 1.5m depth followed by firm silty clay to 1.85m, sand and gravel to 7.6m and stiff London Clay to the base of the borehole at 15.0m. Water at 4.9m and seepage at 4.55m
 - TQ27NW/924 Exploration Associates borehole from 1995: located beneath the current bottling plant in the eastern part of the site. Encountered made ground to 1.4m depth followed by sand and gravel to 4.8m and very stiff London Clay to the base of the borehole at 15.0m. Groundwater not encountered during drilling

4.0 CURRENT SCL EXPLORATORY WORK

The SCL fieldwork was carried out in October 2016 and comprised the elements detailed below. The exploratory positions were determined following discussions with Waterman Structures Ltd. Sampling procedure for the environmental samples was in accordance with BS10175 and WI&E requirements. UXO specialist site attendance provided detection/clearance during the works.

Cable percussion boreholes

4no cable percussion boreholes (BH1 and BH2, 2A, 2B) were constructed using a cable percussion drilling rig. A summary of depths and inferred ground levels is given in the table below.



BH	Ground Elevation*	BH depth (below ground level)
1	+5.15m OD	30.00m
2	+4.81m OD	3.60m
2A*	+4.80m OD	3.50m
2B	+4.96m OD	30.00m

(Levels from GPS survey except for 2A whose level was inferred from the site survey drawing)

BH2 and BH2A were terminated due to encountering impenetrable concrete obstructions.

In situ Standard Penetration Tests (SPTs) were undertaken at regular intervals and representative soil samples, both disturbed and relatively undisturbed, collected for description and for testing.

The calibration certificate for the cable percussive drilling rig SPT equipment used indicates that Energy Ratio, Er, of 66% should be used to provide corrected N_{60} values in line with the recommendations given in BS EN 22476-3, 2005, National Annex A.

Dynamic sampler boreholes and dynamic probe tests

15no dynamic (windowless) sampler boreholes (WS1 to WS7, WS7A, WS8, WS8A, WS9, WS9A, WS10. WS10A and WS11) were completed using a small tracked rig, under the supervision of SCL, to depths of up to 5.5m bgl. SPTs were carried out in the natural strata and disturbed samples were taken for subsequent laboratory testing. Several of the boreholes were refused on obstructions within the made ground – WS6 at 0.5m, WS7 at 0.8m, WS7A at 1.4m, WS8 at 1.0m, BH10 at 1.6m, and WS11 at 0.7m depth.

The calibration certificate for the dynamic sampler drilling rig SPT equipment used indicates that Energy Ratio, Er, of 79% should be used to provide corrected N_{60} values in line with the recommendations given in BS EN 22476-3, 2005, National Annex A.

PID testing

PID (photo-ionisation detector) headspace testing was undertaken during the fieldwork on all made ground and shallow natural soil samples, and the results are shown on the relevant exploratory records in the Appendix.

Groundwater and gas installations

50mm ID HDPE monitoring standpipes were installed in most of the boreholes (with the exception of WS3, 6 & 11) into the London Clay Formation, with a filter/response zone generally within the Made Ground, to facilitate water/gas monitoring by Waterman Infrastructure & Environment.

A summary of the borehole installations is provided below:



Summary of pipe installation							
Installation reference	Pipe tip		Response zone				
(and nominal internal pipe diameter)	Depth (m bgl)	Approx. elevation (m OD)	Depth (m bgl)				
BH1	6.00	-0.85	1.00 to 6.00				
BH2B	5.00	-0.05	1.00 to 5.00				
WS1	5.00	+1.12	1.00 to 5.00				
WS2	2.00	+4.10	1.00 to 2.00				
WS4	5.00	+0.85	2.00 to 5.00				
WS5	5.00	+0.76	2.00 to 5.00				
WS7A	1.40	+3.83	0.50 to 1.40				
WS8A	2.50	+2.65	1.00 to 2.50				
WS9A	3.70	+1.20	1.00 to 3.70				
WS10A	4.00	+0.90	1.00 to 4.00				

Geotechnical laboratory testing

The following geotechnical laboratory testing was completed:

- Natural moisture content and index properties tests (Atterberg Limits)
- Undrained triaxial testing
- Particle size distribution
- Soluble sulphate/pH analyses (tested by QTS Environmental Ltd)

The borehole records are included in the Appendix, together with a Site Plan which shows the exploratory locations.

5.0 GEOLOGY AND GROUND CONDITIONS

Reference to published 1:50,000 scale BGS map indicates that the site is underlain by Kempton Park Gravel Formation, overlying the London Clay Formation, shown to extend to at least 45m depth in nearby historical boreholes. Alluvium, associated with The River Thames, is shown along the southern bank of The Thames, immediately to the north of the site. Historical BGS borehole from the 19th and early 20th centuries at the brewery site indicate that the London Clay Formation is about 60m thick and the chalk is present (below the Lambeth Group and Thanet Beds) at about 81m to 83m depth below ground level.

The various ground investigations (as discussed in Section 3.0) at the site confirmed the anticipated upper sequence as summarised below. The appended strength/depth graph and cross sections through boreholes should also be referred to as they readily illustrate the sequence.



It must be understood that the following summary is based on generally widely spaced boreholes (up to about 100m) and hence there can be expected to be further variation between these positions.

5.1 Made ground

Hard surfacing across the site comprised concrete (some reinforced) and/or asphalt. The underlying made ground typically ranged in thickness between about 1.0m and 3.0m, but locally, at the west of the site was <1.0m thick. In the extreme east, thicknesses of up to 4.6m of made ground were recorded.

The made ground varied in composition both laterally and vertically over short distances. It generally comprised variable, non-engineered mixtures of grey or brown silty sand, locally clay, and gravel size pieces of mostly concrete, flint and brick but also stone, asphalt, clinker, glass, metal, wood and occasional cobble to boulder size concrete and brick pieces. Obstructions from former structures were commonplace in the eastern part of the site, where made ground thicknesses were the greatest, with likely buried/infilled basements being present. The backfill to numerous service runs can also be expected. Several of the boreholes were terminated within concrete obstructions at this part of the site, between about 3.0m and 3.6m depth bgl.

5.2 Alluvium

Alluvium was recorded beneath the made ground in fourteen of the fifty one borehole records we have reviewed, which includes the current boreholes. Where present, the stratum was 0.35m to 1.5m thick (averaging about 0.9m), reaching depths of between 1.5m and 2.8m bgl, and approximate levels ranging between +3.0mOD and +4.9mOD. The stratum generally comprised brown/dark brown, locally grey/orange mottled clay/sandy clay, with occasional to some flint gravel. Occasional roots were also noted. The consistency of the clay was assessed as generally being soft, locally firm.

The distribution of the alluvium across the site has no discernible trend, being recorded in several boreholes in the southern area of the eastern part of the site, and, more frequently, at various locations across the western half. It is thus likely that this natural stratum has been removed from much of the site by the previous development and is now replaced by made ground.

Plasticity Indices (PI) of 14% and 19% and Liquid Limits of <40% were measured on two samples, indicating the alluvium to be low to intermediate plasticity (BS classification) and a low volume change potential (NHBC classification).

5.3 Kempton Park Gravel

The Kempton Park Gravel was present in almost all boreholes where the made ground was fully penetrated and described as brown or light brown, locally greyish or orange brown mixture of slightly silty/silty sand and gravel, locally clayey or very clayey. The gravel comprised fine to coarse flint.

The stratum attained a thickness of between 1.2m and 5.95m (averaging 3.67m), and where proven, extended to depths of between 3.7m and 7.6m bgl (average of 5.3m). We do not have information on the ground levels at the time of the historical investigations, however, assuming these were similar to the current ground levels these depths correspond to an elevation of approximately +1.2mOD to -0.65mOD across the site, generally rising from west to east. A single borehole record (BGS borehole 398), constructed in the southern central area of the site, identified that the base of the gravel possibly occurs



at about -1.7mOD. This is greater localised depth than recorded elsewhere may be due to either a) a higher ground level being present when the borehole was drilled or b) deeper geological scouring by the gravel.

An indicative plan in the Appendix gives approximate depth zones to the top of the stratum, based on all available boreholes. The top of the gravel stratum beneath the vast majority of the western site, and the central area of the eastern half of the site, are indicated to be in the range of 1m to 2m depth bgl, whilst the western and south-eastern corner of the western half of the site, and both the northern and southern zones of the eastern half are indicated to have a thicker made ground/alluvium, with the top of the gravel stratum occurring at 2m to 3m bgl. Local areas of either shallower or deeper occurrences are also recorded in part of the west and the extreme east of the overall site. In the east (BH GE03) the gravel was absent with the made ground resting upon the London Clay at 4.6m depth.

SPT N₆₀ values of between 13 and >50 blows were measured by SCL, indicating a variable medium dense to very dense state of compaction. A few results from the historical boreholes are also available giving a similar range of values, although there is no SPT hammer energy information available to produce a 'corrected' N₆₀ values, thus direct comparison with the current results is not possible.

Particle size distribution tests from the SCL boreholes indicated a predominance of sand (between 32% and 93%) with gravel (generally between 5% and 68%), together with low fines (clay and silt) content ranging between 1% and 13%. It should be noted that the drilling through the granular strata necessitated the addition of water which may have washed out some of the fines from the samples with the results that fine particles may be under-represented in the tests.

5.4 London Clay Formation

The London Clay Formation was encountered beneath the Kempton Park Gravel (where penetrated), and at one of the historical boreholes in the east of the site, directly beneath made ground at 4.6m depth. It generally comprised brown/dark brown (weathered) with depth becoming dark greyish brown/grey fissured clay with occasional partings/pockets of silt/fine sand, occasional silty/slightly sandy zones, small infilled burrows, shell fragments and claystone nodules. It was necessary to undertake chiselling techniques to bypass these claystones.

The top of the London Clay was present at between 3.7m and 7.6m bgl (average of 5.3m) depth bgl (about +1.2mOD and -1.7mOD across the site) and a thin layer of reworked clay, up to 0.3m thick, containing flint gravel, was recorded locally. Whilst some of the boreholes recorded the upper zone of the clay to be brown, others did not, which indicates a variable weathered profile. The depth to the top of the London Clay across the site is shown in the indicative zone plan in the Appendix, indicating a deepening from 3m to 4m bgl in the south-east to a depth of 5m to 6m in the north-west across the eastern half of the site. Only limited data are available for the western half of the site (only covering the south-eastern corner), and these indicate depths to the top of the clay to from 5m to 6m range to 7m to 8m depth from south to north.

Plasticity Indices (PI) of >40% and Liquid Limits of >70% were measured, indicating the London Clay to be very high plasticity (BS classification) and a high volume change potential (NHBC classification).



In situ SPTs and triaxial testing indicate that the clay strength increases with depth, from an initially medium to high strength (minimum c_u of around 60kPa) at the top of the stratum, becoming very high strength below about 10m to 15m depth. The strength vs depth profile is shown in the Appendix.

The London Clay was present to the full depth investigated, maximum of 30m bgl in our boreholes at the eastern half of the site (about -25mOD minimum); historical BGS boreholes indicate a thickness of around 60m beneath the site.

5.5 Groundwater

Groundwater inflows were noted within the Kempton Park Gravel in SCL BH1 (at 4.3m sealed out by the casing at 5.0m) and in BH2B (at 3.20m sealed out at 4.15m). In the deeper dynamic sampler boreholes water was recorded at between about 2.9m and 4.5m depth, whilst several of the boreholes remained dry throughout.

The historical BGS boreholes recorded groundwater depths at about 4.5m and 6.1m bgl. The Ground Explorations 1980 investigation reported water at between about 2.6m and 4.0m, and the SCL boreholes of 2004 recorded groundwater within the superficial deposits at between 5.1m and 5.6m depth. More recently, groundwater monitoring by AECOM indicated water depths ranging between 3.57m and 5.14m bgl. A small tidal influence (of 60mm) was measured over a short period of 2.5 days – although it is not stated whether this reflects a Spring tide condition where the water range differences between low and high tide are at their highest.

Standpipe monitoring was undertaken by Waterman following the current investigation fieldwork and the results at the time of writing are summarised below:

Summary of available groundwater monitoring by WIE								
Installation reference	Approxim base	ate pipe	Water de 27 Octob	epth/level per 2016				
(all pipe 50mm ID)	Depth (m bgl)	Elevation (m OD)	Depth (m bgl)	Elevation (m OD)				
BH1	5.87	-0.72	3.82	+1.33				
BH2B	4.90	+0.06	3.51	+1.45				
WS1	4.70	+1.42	4.48	+1.64				
WS2	2.07	+4.01	Dry	N/A				
WS4	4.49	+1.36	4.10	+1.75				
WS5	3.18	+2.58	3.09	+2.67				
WS7A	4.52	+0.71	4.42	+0.81				
WS8A	2.42	+2.73	Dry	N/A				
WS9A	0.85	+4.05	Dry	N/A				
WS10A	3.90	+1.00	2.30	+2.62				

Notes:

1) Ground levels from GPS survey

2) Pipe base shown is as measured during monitoring – reflecting some silting up of the installation

There is no current information available for the western half of the site, however, the recorded levels in the eastern half are similar to those recorded historically and we do not anticipate significant variations between the eastern and western halves of the site. Some variability should, however, be expected due



to former structures and geological variations. Seasonal variations and some tidal influence should also be anticipated.

5.6 Environmental observations

No visual or olfactory signs of gross contamination were observed in any of the strata and all PID headspace measurement indicated nil or very low concentrations of volatile hydrocarbons (all <5ppm with the exception of three results, maximum 16.3ppm) within the made ground and upper natural soils. Asbestos containing materials (ACMs) were not visually observed in our boreholes but these are common in made ground and in buildings constructed before 2000. Reference should be made to the WIE report in this regard.

6.0 PRELIMINARY GEOTECHNICAL ASSESSMENT

The overall scheme proposal (Phases 1, 2 and3) is to demolish the existing buildings and infrastructure, and redevelop the site with educational, commercial, retail, leisure and residential apartment blocks, with a single storey basement to provide car parking facilities and plant rooms to the development. A minimum headroom height in the proposed basement is to be approx. 4.0m to 4.5m and a raft thickness of approx. 850mm thick is proposed. The total excavation depth is expected to be up to about 7m, equating to an elevation of approximately -2.0mOD.

There will be a mix of building heights across the site of between 3-8 storeys. The residential blocks are likely to be concrete framed buildings utilising flat slab construction on in situ reinforced concrete columns. The proposed structure for the retail/leisure buildings is envisaged to be steel framed with composite beams and floors.

Available architectural drawings showing the proposed construction are appended.

6.1 Basement excavation and retaining wall

Based on the available borehole records, the excavation for the proposed basement, which is expected to be about 7.0m deep, will generally encounter a sequence of variable made ground, locally followed by alluvium, and then the Kempton Park Gravel. The available borehole records indicate that the London Clay Formation would be encountered at the lower part of the basement excavation, in some areas towards/at the base of the excavation, but at this stage we have insufficient deep borehole information to fully assess the geological sequence at the western half (Phase 3) of the overall site in particular.

Based on limited/partial available information depth to the London Clay Formation appears to deepen (and be at a lower elevation) from east to west within the Phase 1 and 2 area, and within the Phase 3 area it appears to be slightly deeper.

From the historical information and recent monitoring in 2016 (by Waterman), steady-state groundwater levels are expected to be around 1.5m to 3.5m above the formation level, within the superficial deposits and made ground, although this must be verified by further monitoring as levels may rise during wet periods. Limited information available at the time of writing, from a previous investigation by AECOM,



indicates that tidal influences are not thought to be significant, however, we would recommend additional monitoring work is undertake to verify these results, as the monitoring period undertaken previously was only for 2.5 days and it is not clear whether it coincided with the highest tidal range.

As a relatively high groundwater is present we consider that an embedded water-tight retaining wall construction will be required to permit basement excavation and stop any water ingress; a sheet pile or secant bored pile wall will probably be the optimum type. Where the excavation is likely to adversely affect any remaining structures/infrastructure, a robust arrangement of temporary internal bracings/props, including support elements near the top of the basement wall, will be required to maintain wall stability and assist in controlling ground movements. The presence of reported previous basements and deep concrete obstructions, particularly in the eastern half (Phase 1 and 2) of the site, must be considered in the choice of retaining wall and measures to remove the obstructions will have to be carefully considered to avoid installation difficulties.

Careful selection of the appropriate temporary design parameters will be needed, incorporating allowances for factors such as the presence of groundwater and the possibility of soil softening – CIRIA Report C580 provides more detail.

In the permanent case the lateral earth pressures will be supported directly by the piled retaining wall or by a reinforced concrete lining wall cast within the piles. In either case horizontal support to the wall will be provided by the new ground and basement floor slabs.

Stratum	Bulk density (Mg/m³)	Effective cohesion, c' (kN/m²)	Effective friction angle, ¢ (degrees)
Made ground and alluvium	1.80	0	25
Kempton Park Gravel	2.00	0	36
London Clay:			
<5m below basement level	2.00	0	22
>5m below basement level	2.00	5	22

The following table of coefficients may be used for the preliminary design of the basement retaining wall:

The wall designer should use these parameters to derive the active and passive earth pressure coefficients, Ka and Kp. The determination of appropriate earth pressure coefficients, together with factors such as the pattern of earth pressure distribution, will depend upon the type/geometry of the wall and the overall design approach. Piled walls may of course also be used to provide vertical load capacity if required subject to the necessary allowance being made for interaction effects.

A specialist contractor/structural engineer must be consulted to confirm the most appropriate type of wall and to provide the final wall design.

6.2 Basement raft design

The current proposals are for a very large basement extending beneath the vast majority of the site. We understand that current proposals envisage the use of a reinforced concrete basement raft and consider that this should provide an eminently suitable foundation solution. We recommend that a detailed ground movement analysis is undertaken in due course to provide the design/performance information based on the findings of the ground investigations; such an analysis is outside the scope of this current report.

The basement excavation will involve the removal of approximately 7m of soil, resulting in unloading of about 130kN/m². This stress reduction will theoretically result in an element of heave in the London Clay beneath the site. The potential long term effect of this heave in the London Clay as it recovers should be considered during raft design and the raft must clearly be designed to withstand potential forces/movements. The stresses within a large raft will be complex and will be highly dependent on the column spacing and the relative soil and structure stiffnesses. There may be areas of net unload where some heave would be expected, with other areas of net loading where downward settlements will occur. As discussed above, these raft movements should be analysed in due course by a specialist ground movement analysis.

It will also be necessary to consider uplift of the raft due to potential hydrostatic pressures and in this respect the guidelines incorporated in BS8102:2009 should be followed. The raft design will need to take account of potential seasonal fluctuations and/or accidental/tidal and flood conditions. At this stage, subject to further monitoring and detailed hydrogeological assessment (outside our current scope) we consider that a design water level of say 2m below ground level could be used for preliminary design. Based on this water level we consider that a theoretical hydrostatic uplift pressure of 50kN/m² should be used for raft design (for a 7m deep excavation). This preliminary value can be regarded as the minimum design uplift pressure for the basement raft. This design water level may need to be agreed with the local building control in due course.

We understand that the site is within Flood Zones 2 & 3 and the potential effects from flooding should also be carefully considered in the design.

6.3 Piled foundations

Piles are envisaged to form the basement retaining walls and may also be required to carry structural loads as part of the retaining wall structure or within other areas of the site. For the ground conditions encountered, with groundwater being present within the superficial soils, we consider that CFA piles are likely to present the optimum type for load-bearing. Obstructions must be expected, some at depth within the made ground and these will require removal prior to piling.

The following table of coefficients may be used for the design of CFA piles, based upon the measured strength/level profile included in the Appendix.



Shaft adhesion

Stratum	Depth/level	Undrained cohesion (from strength profile)	Ultimate unit shaft adhesion `q₅′
All made ground and	Above 7.0m depth	Ignore	Ignore
natural strata (above	(about -2.0mOD)		
basement excavation)			
London Clay	Below 7.0 depth	Increases linearly from	Increases linearly from 45kN/m ²
Formation	(about -2.0mOD)	90kN/m ² at a rate of	at a rate of 4.72kN/m ² /m
		9.44kN/m²/m	(incorporates $\alpha = 0.50$)

Notes:

a) Unit shaft adhesion 'q_s' = $\alpha \times c_u$ (where $\alpha = 0.50$ and c_u is the undrained cohesion from the design line)

b) The α value of 0.5 is based upon 102mm diameter triaxial tests and this should not be varied

c) The average shaft adhesion over the pile length should be limited to 110kN/m^2

d) The maximum value for unit shaft adhesion should be limited to $140 \mbox{kN/m}^2$

End bearing

Stratum	Depth/level	Undrained cohesion	Ultimate unit base resistance
		(from strength profile)	`q₅′
London Clay	Below say 15m depth	Increases linearly from	Increases linearly from
	(-10.0m OD approx)	165.5kN/m ² at a rate of	1,489.5kN/m ² at a rate of
		9.44kN/m²/m	85kN/m²/m
			(incorporates Nc = 9)

Notes:

a) Unit base resistance in clay $q_b' = Nc \times c_u$ (where Nc = 9 and c_u is the equivalent undrained cohesion from the design line)

Using the traditional UK approach, an overall Factor of Safety of 2.6 should be appropriate when applied to these ultimate parameters, in accordance with the LDSA guidelines. Example working loads are provided below:

Pile diameter (mm)	Pile toe depth (m bgl)	Ultimate load (kN)	Working load (kN)
450	15	960	370
	20	1695	650
	25	2600	1000
600	15	1385	530
	20	2395	920
	25	3630	1395
750	15	1860	715
	20	3165	1215
	25	4745	1825
900	15	2395	920
	20	4000	1540
	25	5940	2285

Notes:

a) Working load is calculated using F_{shaft} and F_{base} = 2.6

b) Concrete stress should be considered in the final design

c) Pile length assumes top of pile at 7m depth (approximately -2.0mOD)

d) Pile capacities are given as a guide and are not constituted as design recommendations



Although groundwater inflows were not observed within the London Clay, it is noted that groundwater seepages may occur within the stratum, especially in silty/sandy zones or where claystones are present. Some modification of the pile parameters or downgrading of the pile capacities may be warranted to mitigate the possible risk of clay softening, although this should be minimal with well-installed CFA piles.

Any piles within the heave zone may be subject to an element of uplift as the clay responds to the excavation unloading, with tensile forces being generated within the shaft. The maximum tensile forces will occur if the piles are installed prior to the excavation (for example single piles with plunge columns), but even if installed following the basement excavation they could still be subjected to some tension until the axial loads are applied by the new structure. The final pile design should address the potential tensile forces and appropriate reinforcement should be incorporated.

Eurocode 7 adopts a slightly different approach, applying partial factors to the ultimate pile capacity in accordance with EC7 (BS EN 1997-1:2004 and UK National Annex) for the ultimate limit state GEO Design Approach 1, Combinations 1 and 2. The following partial factors, as recommended in the UK National Annex, are applied:

a]	Model Factor, γ_{Rd}	=	1.4 (Combinations 1 and 2)
b]	Factor on shaft resistance, $\gamma_{\rm s}$	=	1.6 (Combination 2)

c] Factor on base resistance, γ_b = 2.0 (Combination 2)

When designing to EC7, the engineer must ensure that the correct comparisons are made between the Design Actions and Design Resistances. Whilst the partial factors address ULS design, serviceability checks should also be carried out.

We recommend that a specialist piling contactor is consulted at an early stage to advise on the most appropriate pile type and to ultimately provide the final pile design. If pile testing is undertaken it is probable that a lower overall factor of safety could be adopted.

6.4 Foundation concrete

Concentrations of soluble sulphates were measured in selected soil and groundwater samples as follows:

- SCL (10no samples): water soluble sulphate range <10 to 251mg/kg and pH 7.4 to 9.3
- Waterman IE (5no samples): water soluble sulphate range 23 to 472mg/kg and pH 8.5 to 11.2
- **4** AECOM (14no groundwater samples): soluble sulphate <2 to 457mg/kg and pH of 7.1 to 8.1

The older results from the previous investigations have not been included in this assessment as there is no reliance on these results.

The above values result in an overall Site Design Class DS-1/AC-1, as provided in BRE Special Digest 1 (2005), Table C2 for cases where soil oxidation is not anticipated (for example for piling). However, the results suggest that the London Clay is probably pyritic at this site, with many of the oxidisable sulphide levels significantly exceeding 0.3%. Our preliminary recommendation is that that buried concrete which is in contact with soils that have been disturbed/potentially oxidised is designed in accordance with ACEC Site Class AC-4.



Further testing (on both water and soil samples) is being undertaken by WIE as part of the environmental assessment which must be reviewed for final design.

6.5 Further geotechnical investigations

Further comprehensive ground investigations and monitoring of water levels will be required prior to final scheme design.

The current preliminary exploratory work was restricted to Phase 1 and 2 (the eastern half of the global site) and within this area there are significant distances of up to 100m between exploratory positions. In addition contractual reliance may not be available upon some information we have reviewed; particularly the Ground Explorations report of 1980; this information will certainly be outside any warranty period. The BGS Borehole data similarly is provided publicly for information purposes only. The majority of the dynamic sampler boreholes are also of insufficient depth to provide much useful geotechnical design information. Therefore, further investigations should comprise a series of deep boreholes to confirm the levels of the various strata and the groundwater regime, in order to provide sufficient pile and basement design information.

In the Phase 3 (western half of the global site) there are very little data which can be relied upon. Presumably the Client can obtain reliance on the data in the SCL 2004 report; we would have no objection to this but again the information will be outside any warranty period. The BGS information should be used for general background information only. Therefore, in this phase a comprehensive geotechnical investigation will be required, essentially across the whole of the area, again comprising a series of deep boreholes to confirm the levels of the various strata and groundwater regime to provide pile and basement construction design information.

Of course these additional investigations can be undertaken in tandem with WIE to efficiently provide the necessary environmental coverage.

As we have discussed above, a detailed ground movement analysis will be required to assess the performance of the proposed raft. In addition, a hydrogeological assessment is likely to be required for final scheme design.



GENERAL INFORMATION, LIMITATIONS AND EXCEPTIONS

Unless otherwise stated, our Report should be construed as being a Ground Investigation Report (GIR) as defined in BS EN1997-2. Our Report is not intended to be and should not be viewed or treated as a Geotechnical Design Report (GDR) as defined in EN1997-2. Any 'design' recommendations which are provided are for guidance only and are intended to allow the designer to assess the results and implications of our investigation/testing and to permit preliminary design of relevant elements of the proposed scheme.

The methods of investigation used have been chosen taking into account the constraints of the site including but not limited to access and space limitations. Where it has not been possible to reasonably use an EC7 compliant investigation technique we have adopted a practical technique to obtain indicative soil parameters and any interpretation is based upon our engineering experience and relevant published information.

The Report is issued on the condition that Soil Consultants Ltd will under no circumstances be liable for any loss arising directly or indirectly from ground conditions between the exploratory points which differ from those identified during our investigation. In addition Soil Consultants Ltd will not be liable for any loss arising directly or indirectly from any opinion given on the possible configuration of strata both between the exploratory points and/or below the maximum depth of the investigation; such opinions, where given, are for guidance only and no liability can be accepted as to their accuracy. The results of any measurements taken may vary spatially or with time and further confirmatory measurements should be made after any significant delay in using this Report.

Comments made relating to ground-water or ground-gas are based upon observations made during our investigation unless otherwise stated. Ground-water and ground-gas conditions may vary with time from those reported due to factors such as seasonal effects, atmospheric effects and and/or tidal conditions. We recommend that if monitoring installations have been included as part of our investigation, continued monitoring should be carried out to maximise the information gained.

Specific geotechnical features/hazards such as (but not limited to) areas of root-related desiccation and dissolution features in chalk/soluble rock can exist in discrete localised areas - there can be no certainty that any or all of such features/hazards have been located, sampled or identified. Where a risk is identified the designer should provide appropriate contingencies to mitigate the risk through additional exploratory work and/or an engineered solution.

Where a specific risk of ground dissolution features has been identified in our Report (anything above a 'low' risk rating), reference should be made to the local building control to establish whether there are any specific local requirements for foundation design and appropriate allowances should be incorporated into the design. If such a risk assessment was not within the scope of our investigation and where it is deemed that the ground sequence may give rise to such a risk (for example near-surface chalk strata) it is recommended that an appropriate assessment should be undertaken prior to design of foundations.

Where spread foundations are used, we recommend that all excavations are inspected and approved by suitably experienced personnel; appropriate inspection records should be kept. This should also apply to any structures which are in direct contact with the soil where the soil could have a detrimental effect on performance or integrity of the structure.

Ground contamination often exists in small discrete areas - there can be no certainty that any or all such areas have been located, sampled or identified.

The findings and opinions conveyed in this Report may be based on information from a variety of sources such as previous desk studies, investigations or chemical analyses. Soil Consultants Limited cannot and does not provide any guarantee as to the authenticity, accuracy or reliability of such information from third parties; such information has not been independently verified unless stated in our Report.

Our Report is written in the context of an agreed scope of work between Soil Consultants Ltd and the Client and should not be used in any different context. In light of additional information becoming available, improved practices and changes in legislation, amendment or re-interpretation of the assessment or the Report in part or in whole may be necessary after its original publication.

Unless otherwise stated our investigation does not include an arboricultural survey, asbestos survey, ecological survey or flood risk assessment and these should be deemed to be outside the scope of our investigation.



APPENDIX

Fieldwork, in-situ testing

- Cable percussion borehole records
- Dynamic sample borehole records
- Standard Penetration Test (SPT) results
- SPT hammer energy certificates

Laboratory testing and monitoring

- Summary of classification test results
- Plasticity charts
- Particle size distribution results
- Summary of undrained shear strength test results
- Soluble Sulphate/pH results (QTS Environmental)

Ground model/summary plots

- SPT and c_u vs depth
- Depth to top River Terrace Deposits
- Depth to top London Clay Formation
- Schematic geological cross sections

Plans & drawings

- Architectural drawings
- Topographical survey drawings
- 👃 Site Plan
- Location Maps



FOREWORD/GUIDANCE NOTES - CABLE PERCUSSION BORING

GENERAL

The Borehole Records are compiled from the driller's description of the strata encountered, an examination of the samples by our Geotechnical Engineer and the results of in-situ and laboratory tests. Based on this data, the report presents an opinion on the configuration of strata within the site. However, such reasonable assumptions are given for guidance only and no liability can be accepted for changes in conditions not revealed by the boreholes.

BORING METHODS

The Cable Percussion technique of boring is normally employed and allows the ground conditions to be reasonably well established. However, some disturbance of the ground is inevitable, particularly some "softening" of the upper zone of clay immediately beneath a granular soil. The presence of thin layers of different soils within a stratum may not always be detected.

GROUND WATER

The depth at which ground water was struck is entered on the Borehole Records. However, this observation may not indicate the true water level at that period. Due to the speed of boring and the relatively small diameter of the borehole, natural ground water may be present at a depth slightly higher than the water strike. Moreover, ground water levels are subject to variations caused by changes in the local drainage conditions and by seasonal effects. When a moderate inflow of water does take place, boring is suspended for at least 10 minutes to enable a more accurate short term water level to be achieved. An estimate of the rate of inflow is also given. This is a relative term and serves only as a guide to the probable flow of water into an excavation.

Further observations of the water level made during the progress of the borehole are shown including end of shift and overnight readings and the depth at which water was sealed off by the borehole casing, if applicable.

Whilst drilling through granular soils, it is usually necessary to introduce water into the borehole to permit their extraction. When additional water has been used a remark is made on the Borehole Record and the implications are discussed in the text.

SAMPLES

Undisturbed samples of the predominantly cohesive soils are obtained using a 100mm diameter open-drive sampler. In granular soils, disturbed bulk samples are taken and placed in polythene bags. Small jar samples are taken at frequent intervals in all soils for subsequent visual examination. Where ground water is encountered in sufficient quantity, a sample of the ground water is also taken.

IN-SITU STANDARD PENETRATION TESTS

This test is performed in accordance with the procedure given in B.S.1377: 1990. The individual blow count record for each test is given on a separate table. The 'N' value is normally the number of blows to achieve a penetration of 0.3m following a seating distance of 0.15m and is quoted at the mid-depth of the test zone. However if a change of stratum occurs within the test zone then a revised 'N' value is calculated to assess one layer in particular. In hard strata full penetration may not be obtained. In such cases the suffix + indicates that the result has been extrapolated from the limited penetration achieved. Where ground water has affected the measured values, the resultant 'N' value has been placed in brackets since it is unlikely to represent the true in-situ density of the soil.



Site & Location:	Stag Brewer Lower Richr		Road	, Mort	lake,	Londo	on SW	L4 7ET		Borehole No:	BH1
Client:	Reselton Pro	opert	ies Lt	d				Coordinates:	520384E, 175949N	She	eet 1 of 3
Engineer:	Waterman S	Struct	ures	Ltd				Ground Leve	1: +5.15mOD	Report No:	10022/OT
Progre	ss & Observations Samples & Tests Field Test Results (m) (m) (m)			- Legend	end Strata Descriptions			Backfill / Installation			
BH/casing	nced: 04/10/2016 dia: 150mm depth: 5.0m	ES PID	0.50	0.5				MADE GROUND: con and brick - driller's c	icrete [250mm] over compact decription	: concrete	
Hand exca to 1.20m	vated inspection pit	ES PID D ES PID U	1.00 1.00 1.30 1.50 1.50 1.55	0.7	1.20	3.95		Soft brown mottled	sandy CLAY - driller's descript	ion	
	ed between 2.0m to assist drilling	ES	2.00		1.85	3.30			silty gravelly fine to medium ⁻ to rounded, fine to coarse fli		2
		ES PID B SPT/C ES PID B SPT/C	2.50 2.55 2.55 2.55 3.50 3.50 3.55 3.55	0.3 N=39 N ₆₀ =43 0.3 N=25 N ₆₀ =28	3.15	2.00			ightly silty very sandy GRAVE ed, fine to coarse flint	E. Gravel is	3
	er strike at 4.30m ; sealed out at 5.0m	ES PID D SPT/S PID	4.50 4.50 4.70 4.90 5.05 5.05 5.50	0.4 N=15 N ₆₀ =16 0.4	4.70 4.90 5.05	0.45 0.25 0.10		brown, CLAY with ra medium flint gravel	cally mottled dark grey and re re subangular to rounded, fin sured, CLAY. Occasional light surfaces greyish brown CLAY	e to	5
		D	6.00 6.55					at 6.0m; with rare foram for an for a for	ossils		6
BH depth:	t 04/10/2016 7.0m ær depth: dry	D D SPT/S	7.50 8.05 8.05	N=24 N ₆₀ =26	7.50	-2.35		pockets and partings	greyish brown CLAY with freq s of dark grey fine sand and g e white foram fossils		8
		D	9.00 9.55								9
Key: U = U HV = Hand Remarks:	ndisturbed B = Bulk D = Vane [kPa] PID = Photo 50mm ID standp	o Ionisatio	n Detecto	r [ppm - Iso	10.00 5 = glass obutylene	-4.85 jar & plast Equivalen	tic tub E = t, PhoChec	lass jar SPT/S = split spoon : Tiger, 10.6eV lamp] * = ful	Continued on next sheet SPT/C = solid cone PP = Pocket Penetro I SPT penetration not achieved - see su	mmary sheet	10 Borehole type: Cable Percussio Borehole No: BH1
										Soil	Consultants

Site &	Stag Brewe	ry,									Borehole No:	в	Н1
Location:	Lower Rich	mond	Road	, Mortl	ake,	Lond	on SW	14 7ET			borenoie No.	Б	
Client:	Reselton Pr	opert	ies Lt	d					Coordinates:	520384E, 175949N	She	et 2 of 3	
Engineer:	Waterman S	Struct	ures l	Ltd					Ground Level:	+5.15mOD	Report No:	1002	22/OT
Progre	ss & Observations	Sample	s & Tests	Field Test	St	rata	Legend			Strata Descriptions			ckfill / allation
		Туре	Depth (m)	Results	Depth (m)	Level (m)			C		6	×////	
		D	10.50					pockets a	nd partings o	k greyish brown CLAY with f dark grey fine sand and gr vhite foram fossils			
		D SPT/S	11.05 11.05	N=34 N ₆₀ =37	11.05	-5.90		Very stiff,	fissured, dar	k greyish brown CLAY			
		D	12.00					at 12.0m; wi	th rare foram foss	<u>sils and gr</u> ey silt infilled burrows			12 — - - -
		U	12.55					at 12.55m; lo	ocally stiff				13 -
		D D SPT/S	13.50 14.05 14.05	N=35	13.50	-8.35		Occasiona		brown slightly sandy silty C <u>s and g</u> rey silt infilled burro <i>claystone</i>			 14
		D	15.00	N ₆₀ =38									
		U	15.55										
		D	16.50		16.50	-11.35		Very stiff fossils and	dark greyish I grey silt infi	brown silty CLAY. Occasiona illed burrows	al foram		
		D SPT/S	17.05 17.05	N=41 N ₆₀ =45									17 —
		D	18.00										18
		U	18.55										 19
		D	19.50		19.50 20.00	-14.35 -14.85		Very stiff Occasiona	l foram fossil	brown slightly sandy silty C s and grey silt infilled burro ntinued on next sheet	LAY. ws		
Key: U = U HV = Hand	ndisturbed B = Bulk D Vane [kPa] PID = Phot	= Small dis o Ionisatio	sturbed W n Detector	= Water ES	5 = glass butylene	jar & plas Equivalen	tic tub E = t, PhoChec	glass jar SPT/S k Tiger, 10.6eV l	= split spoon SPT amp] * = full SP	/C = solid cone PP = Pocket Penetron T penetration not achieved - see sur	meter [kg/cm ²] nmary sheet	Borehole Cable P	e type: Percussion
Remarks:	50mm ID stand	pipe ins	talled to	6.0m								Borehole	
											Soil	Consulta	ints

Site & Location: Lower Rie		Road	, Mort	lake,	Londo	on SW	Borehole No:	В	H1
Client: Reselton	Propert	ies Lt	d				Coordinates: 520384E, 175949N Shee	et 3 of 3	
Engineer: Waterma	n Struci	ures	Ltd				Ground Level: +5.15mOD Report No:	1002	22/OT
Progress & Observations	Sample	es & Tests	Field Test		trata	Legend	Strata Descriptions		ckfill / allation
	Туре	Depth (m)	Results	Depth (m)	Level (m)		Very stiff dark greyish brown slightly sandy silty CLAY.	~///	
	D SPT/S D	20.05 20.05 21.00	N=46 N ₆₀ =51				Occasional foram fossils and grey silt infilled burrows		21 -
End of shift 05/10/2016 BH depth: 22.0m Groundwater depth: dry	U	21.55					between 22.20m and 22.35m; claystone		22 -
0.5hr chiselling between 22.20m and 22.35m [claystone]	D SPT/S	22.55 23.05 23.05	N=46 N ₆₀ =51						23 -
	D	24.00 24.55							24 - - 25 -
	D D SPT/S	25.50 26.05 26.05	N=51 N ₆₀ =56	26.00	-20.85		Very stiff dark greyish brown CLAY with occasional white shell fragments		- 26 -
	D	27.00							27 -
0.5hr chiselling between 27.40m and 27.60m [claystone]	U	27.55					between 27.40m and 27.60m; claystone		28 -
	D	28.75					at 28.75m; locally silty clay with occasional grey silt infilled burrows		29 -
BH completed: 06/10/2016 Groundwater depth on removal of casing: 3.90m			N=46 N ₆₀ =51	30.00	-24.85		End of hole at 30.00m	Deres 1	30 -
Key: U = Undisturbed B = Bul HV = Hand Vane [kPa] PID = Remarks: 50mm ID sta				5 = glass obutylene	jar & plast Equivalen	tic tub E = 4	Tiger, 10.6eV lamp] * = full SPT penetration not achieved - see summary sheet	Borehole	Percussion e No: H1

Site & Location:	Stag Brewe		Road	, Mort	lake,	Lond	on SW	14 7ET				Borehole No:	В	H2
Client:	Reselton Pr	opert	ies Lt	d					Coordinates:	520410E, 17596	52N	She	et 1 of 1	
Engineer:	Waterman S	Struct	ures	Ltd					Ground Level:	+4.81mOD		Report No:	100	22/OT
Progre	ss & Observations	Sample Type	es & Tests Depth (m)	Field Test Results	Depth	trata Level (m)	Legend		1	Strata Descriptions				ckfill / allation
BH comme BH/casing BH casing of Hand excar to 1.20m 1.5hr chise [possible c 1.5hr chise [concrete b Groundwat [fast inflow 2hr chiselli and 3.60m slab] Borehole te	nced: 03/10/2016 dia: 150mm depth: 3.45m vated inspection pit elling at 1.80m oncrete slab] elling at 2.25m	Type ES PID D SPT/S ES PID ES PID ES PID ES PID	Depth (m) 0.50 0.50 1.00 1.25 1.25 1.50 1.50 2.00 2.00 2.25 2.50 2.50 3.00 3.00		Depth (m)	Level (m)			, steel and c	End of hole at 3.60m				
Key: U = Ur HV = Hand Remarks:	ndisturbed B = Bulk D = Vane (kPa) PID = Phote BH backfilled up			= Water E r [ppm - Iso	S = glass obutylene	jar & plas Equivaler	itic tub E = - tit, PhoCheck	glass jar SPT/S k Tiger, 10.6eV	= split spoon SP lamp] * = full S	7/C = solid cone PP = Po PT penetration not achie	cket Penetrom ved - see sumi	eter [kg/cm²] mary sheet	Borehol	Percussion
												Soil	Consulto	ants

Site &	Stag Brewer	γ,									Borehole No:	Bł	12A
Location:	Lower Richn	nond	Road,	, Mortl	ake,	Londo	on SW	14 7ET					
Client:	Reselton Pro	opert	ies Lte	d					Coordinates:	520651E, 176003N	She	et 1 of 1	
Engineer:	Waterman S	Struct	ures l	_td					Ground Level:	+4.80mOD	Report No:	100	22/OT
Progre	ss & Observations	Sample	es & Tests	Field Test		trata	Legend			Strata Descriptions			ckfill / allation
BH comme	nced 06/10/2016	Туре	Depth (m)	Results	Depth (m)	Level (m)		MADE GR	OUND: aspha	ılt (250mm) over pea shingle	nlastic		
BH/casing	dia: 150mm depth: 2.0m							pipe fragn	nents and cru	ushed concrete - driller's des	cription		
													1 -
Hand exca to 1.20m	vated inspection pit												-
					2.00	2.80		MADE GRO description		hingle and crushed concrete	- driller's		2 —
	er strike at 2.30m /]; not sealed out							description	11				
													3 —
and 3.50m	ng between 3.45m [possible concrete				3.45 3.50	1.35 1.30		MADE GRO	OUND: concre	ete slab - driller's descriptior End of hole at 3.50m	۱/		
slab]													
													-
													5 —
													-
													6 -
													-
													7 —
													-
													-
													8 —
													- 9 —
													-
													10 -
HV = Hand	Vane [kPa] PID = Photo	Ionisatio	on Detector	= Water ES [ppm - Iso	5 = glass butylene	jar & plast Equivalent	ic tub E = t, PhoChec	glass jar SPT/S k Tiger, 10.6eV l	= split spoon SPT lamp] * = full SF	T/C = solid cone PP = Pocket Penetron PT penetration not achieved - see sum	neter [kg/cm ²] mary sheet		ercussion
Remarks:	BH backfilled upo	on com	pletion									Borehole Bł	• No: 12A
											Soil	onsulta	ints

Site & Location:	Stag Brewer Lower Richr		Road	, Mortl	lake,	Lond	on SW	14 7ET			Borehole No:	BH2E	3
Client:	Reselton Pro	opert	ies Lt	d					Coordinates:	520598E, 175976N	She	eet 1 of 3	
Engineer:	Waterman S	Struct	ures	Ltd					Ground Level:	+4.96mOD	Report No:	10022/0	тс
Progre	ss & Observations	Sample	es & Tests	Test	St Depth	rata Level	Legend		I	Strata Descriptions		Backfill , Installatio	
	nced: 07/10/2016	Туре	Depth (m)	Results	(m)	(m)				alt [200mm] over compac	towebod	ার্যা দ্যা	
BH/casing BH casing	dia: 150mm depth: 4.15m vated inspection pit							concrete a					
to 1.20m	vateu inspection pic	ES PID B ES SPT/C	1.50 1.50 2.00 2.00 2.00	0.1 N=36	1.25	3.71		frequent t gravel Dense ora	black flecks a	mottled dark brown, sand nd rare rounded, fine to i slightly silty very gravell o rounded, fine to coarse	y SAND.		2 —
	er strike at 3.20m sealed out at	PID B ES SPT/C PID D	2.00 3.00 3.00 3.00 3.00	$\begin{array}{c} N_{60} = 40 \\ 0.1 \\ \\ N = 14 \\ N_{60} = 15 \\ 0.1 \end{array}$	3.75	1.21		Soft to fir	m dark greyi	ense slightly silty very sandy grav sh brown CLAY with occas edium gravel			3
BH depth:	t 07/10/2016 4.50m ær level: dry	D SPT/S D U	4.05 4.05 4.75 5.05	N=15 N ₆₀ =16	4.05	0.91			red, dark gr	eyish brown CLAY. Rare g	rey silt		4
		D SPT/S D U	6.00 6.55 6.55 7.50 8.05	$\substack{N=23\\N_{60}=25}$	6.00	-1.04		pockets a	nd partings o	eyish brown CLAY with oc if dark grey fine sand. Ra illed burrows			6
	lling between 8.75m [claystone]	D D SPT/S	9.00 9.55 9.55	N=25 N ₆₀ =28	10.00	-5.04		between 8.60)m and 8.75m; c	laystone			9
Key: U = U HV = Hand Remarks:	ndisturbed B = Bulk D = Vane [kPa] PID = Photo 50mm ID standp	o Ionisatio	n Detecto	r [ppm - Iso	1 5 = glass obutylene	jar & plas Equivaler	L stic tub E = nt, PhoChec	l glass jar SPT/S k Tiger, 10.6eV	= split spoon SP	T/C = solid cone PP = Pocket Pene 7 penetration not achieved - see	summary sheet	Borehole type Cable Percus Borehole No: BH2E	e: ssion

Site & Location:	Stag Brewe							Borehole No:	BH2B
Client:	Lower Rich Reselton P			-	lake,	Londo	on Sw	Coordinates: 520598E, 175976N Sheet 2	2 of 3
	Waterman	-						Ground Level: +4.96mOD Report No:	10022/07
Engineer:	Waterman								10022/OT Backfill /
Progr	ess & Observations	Type	Depth	Field Test Results	Depth	Level	Legend	Strata Descriptions	Installation
		.,,,,	(m)		(m) 10.20	(m) -5.24		Stiff, fissured, dark greyish brown CLAY with occasional	
		D	10.50		10.20	-3.24	<u>E</u>	pockets and partings of dark grey fine sand. Rare foram fossils and grey silt infilled burrows Very stiff dark greyish brown slightly sandy silty CLAY with	
								occasional to frequent foram fossils and grey silt infilled lenses. Occasional pockets and partings of fine dark grey	
							E	sand	11 -
		U	11.50						-
		D	12.00						12 -
		D SPT/S	12.55 12.55	N=34 N ₆₀ =37				between 12.55m and 13.55m; locally silty clay	
							<u> </u>		13 -
		D	13.50		13.50	-8.54			
			13.50		13.50	-0.54	E	Very stiff dark greyish brown slightly sandy silty CLAY. Occasional foram fossils and grey silt infilled burrows	
		U	14.05						14
							<u> </u>		-
		D	15.00					at 15.0m; with rare fossil shell debris and frequent foram fossils	15 -
							E		
		D SPT/S	15.55 15.55	N=35 N ₆₀ =38					
									16 -
		D	16.50		16.50	-11.54			
			10.00		10.00	11.01		Very stiff dark greyish brown silty CLAY. Occasional foram fossils and grey silt infilled burrows	-
		U	17.05				E		17 -
							E		-
0 5hr chis	elling between	D	18.00					at 18.0m; pocket of pyrite/pyritic sand	18 -
	nd 18.35m	D	10 55				E	between 18.20m and 18.35m; claystone	
		SPT/S	18.55 18.55	N=39 N ₆₀ =43			E		-
									19
		D	19.50		19.50	-14.54			-
						-		Very stiff dark greyish brown slightly sandy silty CLAY. Frequent foram fossils and grey silt infilled burrows	
- Kara ti					20.00		<u> </u>	Continued on next sheet	20 -
Key: U = L HV = Hand Remarks:					5 = glass butylene	jar & plast Equivalen	tic tub E = t, PhoChec	k Tiger, 10.6eV lamp] * = full SPT penetration not achieved - see summary sheet	orehole type: Cable Percussion orehole No:
	50mm ID stand	ipipe ins		5.UM					BH2B
								SoilCor	nsultants

Site & Location: Lower Rick		Road	, Mort	lake,	Londo	on SW	Borehole No:	BH2B
Client: Reselton P	ropert	ies Lt	d				Coordinates: 520598E, 175976N Shee	t 3 of 3
Engineer: Waterman	Struct	ures	Ltd				Ground Level: +4.96mOD Report No:	10022/OT
Progress & Observations	Sample Type	es & Tests Depth	Field Test Results	Depth	trata Level	- Legend	Strata Descriptions	Backfill / Installation
End of shift 10/10/2016 BH depth: 25.0m Groundwater depth: dry 0.5hr chiselling between 28.00m and 28.15m [claystone]	D D SPT/S D U U D SPT/S D U U D SPT/S D D U U D D SPT/S	 (m) 20.05 21.00 21.55 21.55 22.50 23.05 24.00 24.55 24.55 25.50 26.05 27.00 27.00 27.55 	$N=44 \\ N_{60}=48 \\ N=47 \\ N_{60}=52 \\ N=49 \\ N_{60}=54 \\ N$	(m)	(m)		Very stiff dark greyish brown slightly sandy silty CLAY. Frequent foram fossils and grey silt infilled burrows Very stiff dark greyish brown CLAY with occasional white shell fragments between 28.0m and 28.15m; claystone at 28.75m; locally silty clay with occasional grey silt infilled burrows	21 22 23 24 25 26 26 27 28 28
BH completed: 11/10/2016 Groundwater depth on removal of casing: 3.50m	U	29.55		30.00	-25.04		End of hole at 30.00m	30
Key: U = Undisturbed B = Bulk I HV = Hand Vane [kPa] PID = Ph) = Small di oto Ionisatio	sturbed W	= Water Es	5 = glass	jar & plast Equivalen	ic tub E = t, PhoCheck		Borehole type:
Remarks: 50mm ID stan				Jucylene	_quivalel1	, moched		Cable Percussic Borehole No: BH2B Onsultants

Site & Location:	Stag Brewe Lower Richt		Road	, Mort	lake,	Lond	on SW14 2	7ET				Borehole No:	W	/S1
Client:	Reselton Pr	opert	ies Lt	d					Coordinates:	520396E, 176	5074N	She	eet 1 of 1	
Engineer:	Waterman	Struct	ures	Ltd					Ground Level:	+6.12mOD		Report No:	100	22/OT
Progre	ss & Observations	Sample Type	es & Tests Depth (m)	Field Test Results	St Depth (m)	trata Level (m)	Legend	I		Strata Descriptions				ckfill / allation
BH dia: 10	cted: 04/10/2016 Omm from GL to Icing with depth	ES	0.50		0.50					orced concrete				,
		PID	0.50	0.3	0.60	5.62 5.52	is f MA sar	fine to co ADE GRO Indy grav	oarse flint UND: dark el. Gravel i	gish brown very brown and redd s fine to coarse	ish brown ve	ry clayey		
		ES PID	1.00 1.00	0.3			Ra	are pipe f	ragments					1
		ES PID	1.50 1.50	0.3										
		D	2.20		2.00	4.12				very gravelly SA d, fine to coarse		;		2
		ES PID	2.50 2.50	0.3										
		D SPT/S	3.00 3.00	N=28 N ₆₀ =37			<u>at 3</u>	3.0m; becor	ning dense fine	<u>e to medium</u> sand				3
		ES PID D	3.50 3.50 3.80	0.3	3.80	2.32								
		SPT/S	4.00	N=35 N ₆₀ =46	3.80	2.32				coming orangish angular to roun				4
Groundwat 4.50m	er strike at about	ES PID D	4.50 4.50 4.70	0.2			<u>at 4</u>	4.50m; becc	oming greyish i	brown slightly gravell	y sand			
		SPT/S	5.00	N=21 N ₆₀ =28			<u>at 5</u>	5.0m; becor	ning medium c	lense				5
					5.50	0.62				End of hole at 5.50	n		_	
														6
														7 -
	ndisturbed B = Bulk D Vane [kPa] PID = Phot												Borehol	l e type: ic Sampler
Remarks:	50mm ID stand	pipe ins	talled to	o 5.0m									Borehol	
												Soil	Consulto	-

Site & Location:	Stag Brewe Lower Richt		Pood	Morti	ako	Lond	on SW	1 <i>4</i> 767			Borehole No:	WS2	2
Client:	Reselton Pr				are,	Lonu		14 / 1 1	Coordinates:	520408E, 176037N	She	eet 1 of 1	
Engineer:	Waterman S	-							Ground Level:	+6.08mOD	Report No:	10022/	от
Brogra	sec & Observations	Sample	es & Tests	Field Test	SI	trata	Legend			Strata Descriptions		Backfill Installati	
	ss & Observations	Туре	Depth (m)	Results	Depth (m)	Level (m)			NIND: acnha	Strata Descriptions	concrete	হল চল	
BH dia: 10 1.0m, redu	on completion	Type ES PID ES PID D SPT/S ES PID SPT/S ES PID SPT/S ES PID SPT/S ES PID SPT/S PID	(m) 0.50 0.50 1.00 1.00 1.50 2.00 2.00 2.50 2.50 3.00 3.50 3.50 3.50 4.00	$\begin{array}{c} 0.4 \\ 0.4 \\ 0.3 \\ N=28 \\ N_{60}=37 \\ 0.2 \\ N=34 \\ N_{60}=45 \\ 0.3 \\ N=44 \\ N_{60}=58 \\ 1.5 \\ N=22 \\ N_{60}=29 \\ 0.8 \end{array}$				MADE GR(Gravel is f MADE GR(Gravel is f <i>at 1.40m; con</i> <i>between 1.65</i> <i>at 1.80m; bet</i> Dense ora is subangu to very cla <i>at 3.50m; bet</i> <i>at 3.50m; bet</i>	DUND: light g ine to coarse DUND: orang ine to coarse mand 1.80m; lo coming dark grey ngish brown Jar to angula ayey	slightly to very sandy GRAV r, fine to coarse flint. Local	sand. ndy gravel. te /EL. Gravel		
Key: U = U HV = Hand Remarks:	ndisturbed B = Bulk D Vane [kPa] PID = Phot 50mm ID stand	o Ionisatio	n Detecto	- [ppm - Iso	5 = glass butylene	jar & plas Equivalen	tic tub E = t, PhoCheck	ylass jar SPT/S Tiger, 10.6eV l	= split spoon SPT amp] * = full SP	/C = solid cone PP = Pocket Penetron T penetration not achieved - see sun	nmary sheet	Borehole typ Dynamic Sai Borehole No: WS2 Consultants	mpler : 2
											Soll	Consultants	

Site & Location:	Stag Brewe Lower Richt		Road	, Morti	ake,	Lond	on SW	14 7ET			Borehole No:	w	/ S3
Client:	Reselton Pr	opert	ies Lt	d					Coordinates:	520447E, 176074N	She	et 1 of 1	
Engineer:	Waterman S	Struct	ures	Ltd					Ground Level:	+5.67mOD	Report No:	100	22/OT
Progre	ess & Observations	-	s & Tests Depth	Field Test	St Depth	rata Level	Legend			Strata Descriptions			ckfill / allation
	octed: 04/10/2016 0mm from GL to	Туре	(m)	Results	(m)	(m)				lt (150mm) over dark greyi			=
	icing with depth	ES PID	0.50 0.50	0.4	0.50	5.17 4.67		MADE GRC coarse bri at 0.80m; be flint Orangish	, flint and cor DUND: dark t ck, flint and c coming orangish i coming orangish i brown silty sl SAND. Gravel	prown gravelly clay. Gravel i	s fine to brick and		1
		ES PID D	1.50 1.50 1.60	0.3									
		SPT/S	2.00	N=23 N ₆₀ =30				at 2.0m; bec	oming dense				2 —
		ES PID D	2.50 2.50 2.70	1.8									
		SPT/S	3.00	N=32 N ₆₀ =42									3
		ES PID D	3.50 3.50 3.70	8.8									
		SPT/S	4.00	N=9 N ₆₀ =12	4.00	1.67		Gravel is s		ownish grey slightly gravelly <u>o round</u> ed, fine to medium fl with rare flint			4
		ES PID D	4.50 4.50 4.70	1.3				at 5.0m; bec	oming dense				
BH dry upo	on completion	SPT/S	5.00	N=35 N ₆₀ =46	5.50	0.17				End of hole at 5 50m		-	5
Keuntin										End of hole at 5.50m		Branker	6
Key: U = U HV = Hand Remarks:	Ndisturbed B = Bulk D = Vane [kPa] PID = Phot BH backfilled up	o Ionisatio	n Detecto	= Water ES r [ppm - Isc	b = glass butylene	jar & plas Equivalen	tic tub E = ht, PhoChecl	glass jar SPT/S k Tiger, 10.6eV l	= split spoon SPT amp] * = full SP	/C = solid cone PP = Pocket Penetror T penetration not achieved - see sun	neter [kg/cm ²] mary sheet	Borehole Dynami Borehole	c Sampler
	оп раскніней цр		pieción										/S3
											Soil	Consulto	ints

Site & Location:	Stag Brewe Lower Rich		Road	, Mort	lake,	Lond	on SW	Borehole No:	WS4
Client:	Reselton Pr	opert	ies Lt	d				Coordinates: 520431E, 176031N Sheet	1 of 1
Engineer:	Waterman	Struct	ures	Ltd				Ground Level: +5.85mOD Report No:	10022/OT
Progre	ss & Observations	Sample	s & Tests	Field Test		trata	Legend	Strata Descriptions	Backfill / Installation
BH constru	cted: 04/10/2016	Туре	Depth (m)	Results	Depth (m)	Level (m)		MADE GROUND: asphalt (200mm) over dark brown silty very	য় চা
	0mm from GL to Icing with depth	ES PID	0.50 0.50	0.8	0.80	5.05		sandy gravel. Gravel is limestone, brick and rare flint	
		ES PID	1.00 1.00	0.3				MADE GROUND: dark brown and black slightly sandy slightly gravelly clay. Gravel is fine to coarse clinker, brick and flint at 0.90m; becoming light greyish brown	1 -
		ES PID	1.50 1.50	0.3	1.70	4.15		MADE GROUND: dark brown grey slightly sandy slightly gravelly clay. Gravel is fine to medium clinker, brick and rare concrete fragments	
		ES PID D	2.00 2.00 2.30	0.5	2.00	3.85		Light brown slightly, locally very, gravelly SAND. Gravel is subangular to angular, fine to coarse flint	2 -
		ES PID	2.60 2.60	1.3				at 2.60m; locally stained black	
		D SPT/S	3.00 3.00	N=38 N ₆₀ =50				at 3.0m; becoming very dense	3 -
		ES PID	3.50 3.50	4.2					
		SPT/S	4.00	N=17 N ₆₀ =22				at 4.0m; becoming medium dense	
		ES PID D	4.50 4.50 4.70	3.4					
		SPT/S	5.00	N=9 N ₆₀ =12	5.00	0.85		Firm dark brown CLAY	<u>-</u> 5 -
BH dry upo	on completion	D	5.50		5.50	0.35		End of hole at 5.50m	6 -
									7 -
Key: U = U HV = Hand Remarks:	Vane [kPa] PID = Phot	o Ionisatio	n Detector	- [ppm - Isc	5 = glass obutylene	jar & plas Equivaler	tic tub E = ht, PhoChec	k Tiger, 10.6eV lamp] * = full SPT penetration not achieved - see summary sheet	orehole type: Dynamic Sample orehole No:
KenlarKS:	50mm ID stand	pipe insi	aned to	9 5.UM				Þ	WS4
								SoilCon	nsultants

Site & Location:	Stag Brewe Lower Richt		Road	, Morti	lake,	Londe	on SW	14 7ET				Borehole No:	w	S5
Client:	Reselton Pr	opert	ies Lt	d					Coordinates:	520429E, 17597	'2N	She	et 1 of 1	
Engineer:	Waterman	Struct	ures	Ltd					Ground Level:	+5.76m0D		Report No:	1002	22/OT
Progre	ss & Observations	-	s & Tests Depth	Field Test Results	St Depth	rata Level	Legend			Strata Descriptions		I		kfill / Illation
BH dia: 10	cted: 03/10/2016 0mm from GL to Icing with depth	Type	(m)		(m)	(m)		MADE GRO gravel of o		lt (100mm) over <u>c</u>	greyish bro	own sandy		
		ES PID ES	0.50 0.50 1.00	2.0	0.50	5.26				rey and pinkish g coarse limestone			*	1
		PID	1.00	0.4	1.20	4.56			DUND: dark t el is fine to c	prown slightly sand oarse brick	ly slightly	gravelly		
		PID ES PID	1.50 2.00 2.00	0.5										2
		D	2.30	0.5	2.20	3.56		Gravel is s	ubangular to	htly gravelly sligh rounded, fine to o				-
		ES PID	2.50 2.50	0.8	2.80	2.96			root traces	n brown, becoming	a vellowish	brown,		
		SPT/S D	3.00 3.10	N=16 N ₆₀ =21			* * * * * * * * * * * * *		y SAND with	rare subangular t				3
		ES PID	3.50 3.50	1.1										
Groundwat	er strike at about	SPT/S ES	4.00 4.50	N=40 N ₆₀ =53					ming very dense					4
4.50m		PID D	4.50 4.60	16.3	5.00	0.76		at 4.50m; bei		ty very gravelly sand				5 —
														6
Key: U = Ur HV = Hand Remarks:	Vane [kPa] PID = Bulk D Vane [kPa] PID = Phot 50mm ID stand	o Ionisatio	n Detecto	r [ppm - Isc	5 = giass	jar & plast Equivalen	it, PhoChecl	yıdəs Jar SPT/S k Tiger, 10.6eV l	- эрнс spoon SP1 amp] * = full SP	/C = solid cone PP = Poo T penetration not achiev	ved - see sum	mary sheet	Borehole	c Sampler
												Soil	Consulta	nts

Site &	Stag Brewe	r y ,										Borehole No:	w	/S6
Location:	Lower Richr	nond	Road	, Mort	ake,	Londo	on SW	14 7ET						
Client:	Reselton Pro	opert	ies Lte	d					Coordinates:	520477E, 176066N	N	She	et 1 of 1	
Engineer:	Waterman S	Struct	tures l	Ltd					Ground Level:	+5.22m0D	F	Report No:	1002	22/OT
		Sample	es & Tests	Field	SI	trata								ckfill / allation
	ess & Observations	Туре	Depth (m)	Test Results	Depth (m)	Level (m)	Legend			Strata Descriptions				
BH dia: 10	ucted 05/10/2016 00mm from GL to ucing with depth				0.50	4.72		MADE GR	OUND: concr	ete				
BH refuse	d at 0.50m				0.50	4.72				End of hole at 0.50m				-
														123
														4
														5 -
														6
Key: U = U HV = Hand Remarks:	Indisturbed B = Bulk D = Vane [kPa] PID = Photo BH backfilled up			= Water ES [ppm - Isc	5 = glass butylene	jar & plast Equivalent	ic tub E = t, PhoChec	glass jar SPT/S k Tiger, 10.6eV	= split spoon SP lamp] * = full S	/C = solid cone PP = Pocke PT penetration not achieved	et Penetrome I - see summ		Borehole	<u>c Sampler</u> e No: /S6
												Soil	onsulta	nts

Site &	Stag Brewei	ſγ,									Во	orehole No:	w	IS7
Location:	Lower Richr	nond	Road	, Mortl	ake,	Londo	on SW	14 7ET						
Client:	Reselton Pro	opert	ies Lt	d					Coordinates:	520486E, 176003N		Shee	et 1 of 1	
Engineer:	Waterman S	Struct	ures	Ltd					Ground Level:	+5.23mOD	Re	port No:	100	22/OT
Progre	ss & Observations		es & Tests Depth	Field Test Results	St Depth	rata Level	Legend			Strata Descriptions			Bao Insta	ckfill / allation
BH constru BH dia: 10	cted 05/10/2016 Omm from GL to Icing with depth	Sample Type ES PID					- Legend	MADE GR	OUND: dark (fine to coarse	Strata Descriptions Inced concrete slab greyish brown very san a brick and flint. Locally End of hole at 0.80m	dy grave ' clayey t	el. o very		
Key: U = U HV = Hand	ndisturbed B = Bulk D = Vane [kPa] PID = Photo	Small di	sturbed W on Detector	= Water ES	5 = glass butylene	jar & plast Equivalen	tic tub E = t, PhoChec	glass jar SPT/S k Tiger, 10.6eV	= split spoon SP1 lamp] * = full Sf	-/C = solid cone PP = Pocket P4 PT penetration not achieved - s	enetromete see summar	r [kg/cm²] γ sheet	Borehole	
Remarks:	BH backfilled up	on com	pletion										Borehole	e No:
													W	IS7
												Soil	onsulta	ints

Site & Location:	Stag Brewe		D '	M							Borehole No:	w	S7A
Client:	Lower Rich				аке,	Londo	on SW	14 /ET	Coordinates:	520486E, 176003N	Cha	et 1 of 1	
Engineer:	Waterman S								Ground Level:	+5.23mOD	Report No:		22/OT
			es & Tests	Field	St	trata						Ba	ckfill /
Progre	ess & Observations	Туре	Depth (m)	Test Results	Depth	Level	Legend			Strata Descriptions		Inst	allation
BH constru BH dia: 10	icted 05/10/2016 Omm from GL to Icing with depth	Type		Test	Depth (m) 0.25	Level (m) 4.98	- Legend	MADE GR	arse concrete		Gravel is		
Key: U = U HV = Hand Remarks:	ndisturbed B = Bulk D = Vane [kPa] PID = Phote 50mm ID standg				5 = glass butylene	jar & plast Equivalen	tic tub E = t, PhoChec	ılass jar SPT/S Tiger, 10.6eV	= split spoon SP lamp] * = full SI	T/C = solid cone PP = Pocket Pene PT penetration not achieved - see		Borehole	ic Sampler e No: S7A

Site &	Stag Brewe	r y ,									Borehole No:	•	158
Location:	Lower Richr	mond	Road	, Mortl	ake,	Londo	on SW	14 7ET	1				
Client:	Reselton Pr	opert	ies Lt	d					Coordinates:	520583E, 176026N	She	et 1 of 1	
Engineer:	Waterman S	Struct	ures	Ltd					Ground Level:	+5.15mOD	Report No:	100	22/OT
Progre	ess & Observations	Sample Type	es & Tests Depth	Field Test Results	Depth	rata Level	Legend			Strata Descriptions		Ba Inst	ckfill / allation
BH dia: 10	Incted 03/10/2016 Omm from GL to Juring with depth	ES SPT/S PID	1.00 1.00 1.00	N>50* 0.7	0.70 1.00	(m) 4.45 4.15		MADE GR	fine to coarse	ish brown slightly silty sandy	/ gravel.		
Key: U = U HV = Hand	ndisturbed B = Bulk D = Vane [kPa] PID = Phote	Small di	sturbed W	= Water ES	= glass	jar & plast Equivalent	ic tub E =	glass jar SPT/S k Tiger, 10 6eV	= split spoon SP1 lamp] * = full SI	I/C = solid cone PP = Pocket Penetrom PT penetration not achieved - see sum	neter [kg/cm²] mary sheet	Borehole	e type:
Remarks:	BH backfilled up			[bhu - 120	Juryielle	Lyuvalen	, FIUCHEC	x Hyer, 10.0eV	lun Si	 penetration not achieved - see SUM 	mary sneet	Borehole	<u>c Sampler</u> No: IS8
											Soil	Consulto	ints

Site & Location:	Stag Brewe Lower Richr		Road	, Mort	lake,	Lond	on SW	14 7ET			Borehole No:	WS84	4
Client:	Reselton Pr	opert	ies Lt	d					Coordinates:	520583E, 176026N	She	eet 1 of 1	
Engineer:	Waterman S	Struct	tures	Ltd					Ground Level:	+5.15mOD	Report No:	10022/0	ЭТ
Progre	ess & Observations	Sample Type	es & Tests Depth (m)	Field Test Results	St Depth (m)	rata Level (m)	- Legend			Strata Descriptions	1	Backfill / Installatio	
BH dia: 10 1.0m, redu BH refused	ndisturbed B = Bulk D = Vane [kPa] PID = Photo	Ionisatic	1.50 1.50 2.00 2.50 2.50 2.50	r [ppm - Iso	0.70 1.00 2.40 2.50	4.45 4.15 2.75 2.65	tic tub E = t, PhoChec	MADE GR coarse col MADE GR Gravel is 1 at 2.0m; bec at 2.30m; re Orangish subrounde	acrete and ra	n silty sandy gravel. Gravel are flint n and orangish brown sand e flint and occasional concre grey very clayey sandy gravel <u>o coarse br</u> ick fragments - possible b GRAVEL. Gracvel is subarg	y gravel. tte uried structure gular to ometer [kg/cm ²]	Borehole type Dynamic Sam	npler
Remarks:	50mm ID standp	pipe ins	talled to	o 2.50m								Borehole No:	
											Soil	Consultants	

Site &	Stag Brewe	r y,									Borehole No:	14	/59
Location:	Lower Richr	nond	Road	, Mort	lake,	Londo	on SW	14 7ET			borenoie No.	~~~	39
Client:	Reselton Pro	opert	ies Lt	d					Coordinates:	520517E, 175966N	She	et 1 of 1	
Engineer:	Waterman S	Struct	ures l	Ltd					Ground Level:	+4.89mOD	Report No:	100	22/OT
Progre	ess & Observations	Sample Type	es & Tests Depth	Field Test Results	Depth	trata Level	Legend			Strata Descriptions		Bao Insta	ckfill / allation
BH dia: 10	icted 03/10/2016 0mm from GL to ucing with depth		(m)		(m)	(m)		MADE GR	OUND: aspha	lt (200mm) over concrete			
BH refused					0.50	4.39				End of hole at 0.50m			1
Key: U = U HV = Hand Remarks:	ndisturbed B = Bulk D = Vane [kPa] PID = Photo BH backfilled upo			= Water ES [ppm - Isc	5 = glass bbutylene	jar & plast Equivalent	ic tub E = ;, PhoChec	glass jar SPT/S k Tiger, 10.6eV	= split spoon SPT [amp] * = full SP	/C = solid cone PP = Pocket Penetrom T penetration not achieved - see sum		Borehole	ic Sampler e No: /S9
											Soil	Consulta	ints


Site & Location:	Stag Brewer Lower Richr		Road	. Mort	lake,	Londo	on SW	14 7ET				Borehole No:	W	S9A
Client:	Reselton Pr								Coordinates:	520517E, 17596	56N	She	et 1 of 1	
Engineer:	Waterman S	Struct	ures	Ltd					Ground Level:	+4.89mOD	·	Report No:	100	22/OT
Progre	ess & Observations	Sample	es & Tests	Field Test	S	trata	Legend			Strata Descriptions				ckfill / allation
	icted 12/10/2016	Туре	Depth (m)	Results	Depth (m)	Level (m)	xxxxxxx						নিয়া হিন্দু	r
BH dia: 10 1.0m, redu	Omm from GL to Juding with depth	ES SPT/S PID D HV D HV D HV	2.00 2.00 2.50 3.00 3.00 3.50 3.80 3.90 3.90	N=10 N ₆₀ =13 0.4 N=34 N ₆₀ =45 2.9 70 60	2.00 3.85 4.00	2.89 1.04 0.89		Gravel is f	coming orangish Gravel is fine to ense light bri ND. Gravel i t coming orangish ming dense	brown, grey, brown mot coarse flint, brick and cli brown, grey, brown mot coarse flint and rare bric bown silty slightly g s subrounded to ro brown sandy gravel brown sandy gravel sh grey and reddis rclay End of hole at 4.00m	ttled slightly sa ravelly, loc bunded, fin	ndy slightly ally very e to		
Remarks:	50mm ID standp				Jucylene	Lyuvalen	, mochec	N 11901, 10.00V I	umpj · – Tuli Si	Peneuation not achiev	vou - see suinr	nary sneet	Dynami Borehole	c Sampler e No:
													W	S9A
												Soil	Consulta	ints

Site & Location:	Stag Brewe Lower Richi		Poad	Mort	lako	Lond	on SW	л 7 б т			Borehole No:	w	S10
Client:	Reselton Pr			-	iune,	Lond			Coordinates:	520615E, 176024N	Sh	eet 1 of 1	
Engineer:	Waterman								Ground Level:	+4.92mOD	Report No:		022/OT
			es & Tests		St	rata						Ва	ickfill /
Progre	ess & Observations	Type Depth (m)		Test Results	Depth (m)	Level (m)	Legend	Strata Descriptions				11150	anation
BH dia: 10	ucted 03/10/2016 Omm from GL to ucing with depth	ES PID	0.50	1.1	0.25	4.67		MADE GR	OUND: dark	preed concrete grey sandy gravel. Grav and flint. Locally slightl			
		ES PID	1.00 1.00	0.5									1
BH refused	t at 1.60m	ES PID	1.50	0.5	1.60	3.32				End of hole at 1.60m			
													7 —
Key: U = U HV = Hand	ndisturbed B = Bulk D = Vane [kPa] PID = Phote	= Small di Di Ionisatio	isturbed W on Detecto	= Water Es r [ppm - Iso	5 = glass obutylene	jar & plas Equivaler	tic tub E = o nt, PhoCheck	ass jar SPT/S Tiger, 10.6eV	= split spoon SP lamp] * = full S	T/C = solid cone PP = Pocket Pe PT penetration not achieved - s	enetrometer [kg/cm ²] ee summary sheet		ic Sampler
Remarks:	BH backfilled up	on com	pletion									Borehol	e No: ' S10
											Soil	Consulto	ants

Site & Location:	Stag Brewei	r y ,									Borehole No:	ws	510A
	Lower Richn	nond	Road	, Mortl	ake,	Londo	on SW	14 7ET	1				
Client:	Reselton Pro	opert	ies Lt	d					Coordinates:	520615E, 176024N	She	et 1 of 1	
Engineer:	Waterman S	Struct	ures	Ltd					Ground Level:	+4.92m0D	Report No:	100	22/OT
Progre	ess & Observations	Sample	es & Tests	Field Test	St	trata	Legend			Strata Descriptions			ckfill / allation
		Туре	Depth (m)	Results	Depth (m)	Level (m)	- Legend						
Groundwal about 4.50	Vane [kPa] PID = Photo	Ionisatio	3.80 3.90 4.50 4.50 4.70 4.90 5.00	r [ppm - Iso	2.50 3.70 5.00	2.42 1.22 -0.08	Image: the transmission of the tran	concrete a Light brow rounded, at 3.0m; bec Stiff, local	vn silty SANE fine to coarse oming dense) and GRAVEL. Gravel is sul	pangular to		ic Sampler
Remarks:	50mm ID standp	ipe ins	talled to	94.0m								Borehole	
													510A
											Soil	Consulta	ants

Site &	Stag Brewei	ту ,									Borehole No:	w	S11
Location:	Lower Richr	nond	Road	, Mortl	ake,	Londo	on SW	14 7ET					
Client:	Reselton Pro	opert	ies Lt	d					Coordinates:	520598E, 175976N	She	et 1 of 1	
Engineer:	Waterman S	Struct	ures	Ltd					Ground Level:	+4.96mOD	Report No:	100	22/OT
Progre	ess & Observations	Sample	es & Tests	Field Test	St	trata	Legend			Strata Descriptions			ckfill / allation
		Туре	Depth (m)	Results	Depth (m)	Level (m)				·	h brown		
BH dia: 10	toted 03/10/2016 omm from GL to ucing with depth	ES PID	(m) 0.50 0.50	0.3	(m) 0.70	(m) 4.26		MADE GR sandy gra brick and	vel. Gravel is clinker	It (300mm) over dark greyis s fine to coarse concrete, and End of hole at 0.70m	sh brown i rare		
Key II - I		Small at	sturbed W	- Water FC		jar 0. plact	ic tub E -		- split space CPT		patar [kg/cm ^{2]}	Borehold	
Key: U = U HV = Hand Remarks:	ndisturbed B = Bulk D = Vane [kPa] PID = Photo BH backfilled upo	Ionisatio	n Detector	= water ES [ppm - Iso	b = glass butylene	jar & plast Equivalent	t, PhoChec	yıass jar SPI/S k Tiger, 10.6eV	= spiit spoon SPT lamp] * = full SF	/C = solid cone PP = Pocket Penetron PT penetration not achieved - see sum	meter [kg/cm²] mary sheet	Borehole Dynami Borehole	ic Sampler
												W	S11
											Soil	Consulto	ints

Equipe Group



© Copyright 2015 Equipe Group, The Paddocks, Home Farm Offices, The Upton Estate, Banbury, Oxfordshire, OX15 6HU Tel: +44 (0)1295 670990 Fax: +44 (0)1295 678232 Email: info@equipegroup.com



Dynamic sampling uk Itd 6-8 victory parkway victory road Derby DE24 8ZF

Instrumented Rod Data

Diameter d _r (mm):	54
Wall Thickness t _r (mm):	6.9
Assumed Modulus E_a (GPa):	208
Accelerometer No.1:	6455
Accelerometer No.2:	6457

Hammer Energy Test Report

in accordance with BSEN ISO 22476-3:2005

9 10

9 10


Hammer Ref:	SS01
Test Date:	27/06/2016
Report Date:	
File Name:	SS01.spt
Test Operator:	TP

Hammer Information

Hammer Mass	m (kg):	63.5
Falling Height	h (mm):	760
String Length L	. (m):	15.0

Comments / Location

Hammer tested at Dynamic samplins yard.



The recommended calibration interval is 12 months

SPTMAN ver.Hammer Energy ver. 1.93 All rights reserved, Testconsult ©2010

Site & Stag Brewery,

Location Lower Richmond Road, Mortlake, London SW14 7ET

BH Test 'N' value and blow-counts N_{60} Water Depth Casing Remarks ID [m] depth [m] type [Seating blows/Test blows] depth [m] BH1 2.55 С N = 39 :5 5/ 8 10 10 11 44 2.55 DRY 3.55 С 28 3.55 DRY N = 25 : 4 4 / 6 66 7 5.05 s N = 15 :2 3/3 4 4 4 17 5.00 DRY 5.00 s 27 DRY 8.05 N = 24 :3 3/5 6 6 7 s N = 34 :4 5.00 11.05 4/79 9 9 38 DRY s 14.05 N = 35 :3 4/7 8 10 10 39 5.00 DRY s 17.05 N = 41 : 44/8 10 11 12 46 5.00 DRY s 51 5.00 DRY 20.05 N = 46 : 55/9 11 13 13 23.05 s 51 5.00 DRY N = 46 :5 5/ 9 12 12 13 s 57 5.00 DRY 26.05 N = 51 :5 6/ 10 13 13 15 29.55 s 51 5.00 DRY N = 46 :5 5/ 8 11 13 14 79 s 1.25 BH2 1.25 N = 71 :15 15/ 13 14 20 24 DRY 2.25 С 50 :50 / >56* 0.00 DRY Refusal С BH2B 2.00 N = 36 :4 5/ 7 9 10 10 40 2.00 DRY С 3.00 16 3.00 DRY N = 14 :3 3/3 3 4 4 s 17 4.05 DRY 4.05 N = 15 :2 3/3 4 4 4 s 4.15 6.55 N = 23 :3 3/5 6 6 6 26 DRY s 9.55 N = 25 :3 3/5 6 77 28 4.15 DRY 12.55 s N = 34 :4 4/8899 38 4.15 DRY 15.55 S N = 35 : 55/79910 39 4.15 DRY s 18.55 44 4.15 DRY N = 39 :5 5/ 8 10 10 11 s 49 4.15 DRY 21.55 N = 44 :5 5/9 10 12 13 S 24.55 N = 47 :5 5/9 12 13 13 52 4.15 DRY s 27.55 N = 49 :6 7/ 11 12 13 13 55 4.15 DRY s 37 0.00 DRY WS1 3.00 N = 28 :3 4/7 7 8 6 4.00 S N = 35 :9 10/ 11 9 46 0.00 DRY 8 7 s 0.00 5.00 N = 21 :3 5/6 7 4 4 28 DRY s WS10A 3.00 N = 37 :9 11/ 10 10 10 7 49 0.00 DRY s WS2 37 0.00 DRY 2.00 N = 28 :7 6/7 7 7 7 3.00 s N = 34 :8 8/7 9 8 10 45 0.00 DRY s 58 4.00 N = 44 :9 12/ 12 11 11 10 0.00 DRY s 29 0.00 DRY 5.00 N = 22 :2 3/ 4 6 7 5 WS3 2.00 s 30 0.00 DRY N = 23 :3 5/ 5 6 6 6 3.00 s 42 0.00 DRY N = 32 :7 8/8 8 8 8 4.00 s N = 9 :1 1/ 1 2 3 3 12 0.00 DRY s 0.00 DRY 5.00 N = 35 :4 8/ 7 8 10 10 46 s WS4 3.00 N = 38 :10 9/ 8 10 10 10 50 0.00 DRY s 22 0.00 4.00 N = 17 :7 6/ 5 5 3 4 DRY s 12 0.00 DRY 5.00 N = 9 :3 2/ 2 2 2 3 s 0.00 WS5 3.00 N = 16 :3 3/4 4 4 4 21 DRY s 0.00 4.00 N = 40 :7 7/8 12 10 10 53 DRY WS8 1.00 s 50 :25 / 50 >66* 0.00 DRY WS9A 2.00 S N = 10 :3 2/ 2 3 2 3 13 0.00 DRY Standard Penetration Test : BS EN ISO 22476:2005 Part 3 Hammer Energy Ratio, Er = 66% [CP boreholes] 79% [WS boreholes]

STANDARD PENETRATION TEST SUMMARY

 * where full penetration not achieved, the reported N₆₀ is based on maximum uncorrected blow-counts of 50

** extrapolated N₆₀ value where full penetration not achieved - this is indicative only and should be used with caution

[SPT Sheet 1 of 2]



Site &	Stag E	Report 10022/CH						
Location	Lower	RICI	mond Road, Mortlake, Lo STANDARD PENE			MARY		No:
BH	Depth	Test	'N' value and blow-counts		N ₆₀	Casing	Water	Remarks
		-			45			
ID WS9A	[m] 3.00	type S	[Seating blows/Test blows] N = 34 :7 7/ 7 8 10 9		45	depth [m] 0.00	depth [m] DRY	
Standar	d Penetrati	on Test	: BS EN ISO 22476:2005 Part 3		Hammer Energy I	Ratio, Er = 66	% [CP boreho	les] 79% [WS boreholes]
* where	full penetr	ation no	ot achieved, the reported N_{60} is based or	n maximum und	corrected blow-o	counts of 50		
** extra	apolated N ₆	₀ value	where full penetration not achieved - this	s is indicative or	nly and should t	oe used with	caution	[SPT Sheet 2 of 2]



Site &	Stag Brewery,
Location	Lower Richmond Road, Mortlake, London SW14 7ET

	SUMMARY OF CLASSIFICATION TEST RESULTS										
BH ID	Depth (m)	Туре	w (%)	wL (%)	wP (%)	Pass 425 (%)	IP (%)	Mod IP (%)	IL (%)	LOI (%)	Description
BH1	1.55	U	10	38	19	>95	19		-0.48		Brown sandy CLAY
	4.90	D	33	79	32	>95	47		0.03		Dark brown CLAY
	6.55	U	27								Dark greyish brown CLAY
	9.55	U	26	73	31	>95	42		-0.14		Dark greyish brown CLAY
	12.55	U	26	78	30	>95	48		-0.09		Dark greyish brown CLAY
	15.55	U	20								Dark greyish brown slightly sandy silty CLAY
	18.55	U	26								Dark greyish brown silty CLAY
	21.55	U	25	77	33	>95	44		-0.18		Dark greyish brown slightly sandy silty CLAY
	24.55	U	25	81	33	>95	48		-0.18		Dark greyish brown slightly sandy silty CLAY
	27.55	U	20								CLAYSTONE
BH2B	5.05	U	28	76	32	>95	44		-0.09		Dark greyish brown CLAY
	8.05	U	26								Dark greyish brown CLAY
	11.50	U	25	79	30	>95	49		-0.11		Dark greyish brown slightly sandy silty CLAY
	14.05	U	27								Dark greyish brown slightly sandy silty CLAY
	17.05	U	26	82	31	>95	51		-0.10		Dark greyish brown silty CLAY
	20.05	U	25								Dark greyish brown slightly sandy silty CLAY
	23.05	U	23	79	33	>95	46		-0.23		Dark greyish brown slightly sandy silty CLAY
	26.05	U	25								Dark greyish brown CLAY
	29.55	U	25	78	32	>95	46		-0.16		Dark greyish brown CLAY
Testing i	n accord	tance v	vith RS	FN IS	ם 1780 1780	2 unles	s sneci	ified of	herwise		Date: 01 Nov 16
-											er 4.2 (reported if %passing 425mm <95%)
Percent		-								1- ,	(Classification Sheet 1 of 2)




Report No:


Site &	Stag		-									Report	10022/OT
Location	Lowe	er Ri	chm	ond	Road	d, Mo	ortlal	ke, L	ondo	on S	W14 7ET	No:	
					SU	MMA	RY (CATION TEST RESULTS		
BH ID	Depth (m)	Туре	w (%)	wL (%)	wP (%)	Pass 425 (%)	IP (%)	Mod IP (%)	IL (%)	LOI (%)	Description		
WS10A	3.80	D	31	75	32	>95	43		-0.03		Dark brownish grey CLAY		
	5.00	D	28	77	32	>95	45		-0.09		Dark brownish grey CLAY		
WS5	2.30	D	20	33	18	93	15	14	0.11		Brownish grey slightly gravelly slightly san	dy CLAY	
WS9A	3.90	D	32	75	33	>95	42		-0.02		Dark grey, orangish grey and reddish grey	mottled CL	ΑY
	l Plastici	ty Inde	x calcu	lated ir	n accor	dance v	with NH	IBC Sta	ndards		er 4.2 (reported if %passing 425mm <95%		01 Nov 16
Percent	passing	425µm	: by es	timatio	on, by ł	nand* c	or by si	eving*	*			(Classifica	ition Sheet 2 of 2)

ľ















Sieving									
Size [mm]	% passing								
75	100								
63	100								
50	100								
37.5	100								
28	100								
20	100								
14	99.1								
10	98								
6.3	97.2								
5	96.8								
3.35	96.1								
2	95.2								
1.18	94.5								
0.6	90.7								
0.425	81.6								
0.3	40.8								
0.212	14.6								
0.15	5.9								
0.063	2.1								

Sample proportions	%
Cobbles	0
Gravel	5
Sand	93
Fines <0.063mm	2

Grading analysis		
D60	mm	0.4
D30	mm	0.3
D10	mm	0.2
Uniformity Coefficient		2.0
Curvature Coefficient		1.1

Test method and date	
Testing in accordance with BS EN ISO 17892:	
Wet sieving method	
Reporting date:	08 Nov 16




Sieving	
Size [mm]	% passing
75	100
63	100
50	100
37.5	73.1
28	64.5
20	57.3
14	51.7
10	48
6.3	44.4
5	41.6
3.35	35.6
2	32.5
1.18	30.2
0.6	22.8
0.425	14.7
0.3	5.3
0.212	2.7
0.15	1.4
0.063	0.5

Sample proportions	%
Cobbles	0
Gravel	68
Sand	32
Fines <0.063mm	1

Grading analys	is	
D60	mm	22.7
D30	mm	1.2
D10	mm	0.4
Uniformity Coefficient		63.5
Curvature Coefficient		0.2

Test method and date	
Testing in accordance with BS EN ISO 17892:	
Wet sieving method	
Reporting date:	08 Nov 16






Sieving	
Size [mm]	% passing
75	100
63	100
50	100
37.5	100
28	93.4
20	83.7
14	74.1
10	70.7
6.3	67.2
5	65.5
3.35	62.7
2	59.1
1.18	55.3
0.6	45.9
0.425	36
0.3	16
0.212	5.4
0.15	2.4
0.063	0.8

Sample proportions	%
Cobbles	0
Gravel	41
Sand	58
Fines <0.063mm	1

Grading analys		
D60	mm	2.3
D30	mm	0.4
D10	mm	0.2
Uniformity Coefficient		9.2
Curvature Coefficient		0.3

Test method and date	
Testing in accordance with BS EN ISO 17892:	
Wet sieving method	
Reporting date:	08 Nov 16






Sieving	
Size [mm]	% passing
75	100
63	100
50	100
37.5	100
28	81.7
20	65.3
14	51.1
10	45.3
6.3	41
5	39.2
3.35	36.4
2	34.3
1.18	32.3
0.6	25.7
0.425	18.1
0.3	9.4
0.212	5.6
0.15	4.4
0.063	3.7

Sample proportions	%
Cobbles	0
Gravel	66
Sand	31
Fines <0.063mm	4

Grading analys		
D60	mm	17.5
D30	mm	0.9
D10	mm	0.3
Uniformity Coefficient		57.0
Curvature Coefficient		0.2

Test method and date		
Testing in accordance	e with BS EN ISO 17892:	
Wet sieving method		
Reporting date:	08 Nov 16	




Sieving	
Size [mm]	% passing
75	100
63	100
50	100
37.5	100
28	100
20	100
14	99.4
10	93.7
6.3	86.2
5	83.1
3.35	80.2
2	77
1.18	74.8
0.6	71.3
0.425	67.1
0.3	49.7
0.212	30.8
0.15	18.9
0.063	12.8

Sample proportions	%
Cobbles	0
Gravel	23
Sand	64
Fines <0.063mm	13

Grading analy	sis	
D60	mm	0.4
D30	mm	0.2
D10	mm	
Uniformity Coefficient		
Curvature Coefficient		

Test method and date	
Testing in accordance with BS EN ISO 17892:	
Wet sieving method	
Reporting date:	08 Nov 16






Sieving	
Size [mm]	% passing
75	100
63	100
50	100
37.5	100
28	100
20	98.4
14	91
10	84.1
6.3	77.7
5	75.3
3.35	72.6
2	69.9
1.18	68
0.6	64.7
0.425	61.5
0.3	52
0.212	35.9
0.15	21.2
0.063	8.7

Sample proportions	%
Cobbles	0
Gravel	30
Sand	61
Fines <0.063mm	9

Grading analysis		
D60	mm	0.4
D30	mm	0.2
D10	mm	0.1
Uniformity Coefficient		5.8
Curvature Coefficient		1.2

Test method and date		
Testing in accordance	e with BS EN ISO 17892:	
Wet sieving method		
Reporting date:	08 Nov 16	






Sieving	
Size [mm]	% passing
75	100
63	100
50	100
37.5	100
28	100
20	100
14	94.7
10	90.3
6.3	85.4
5	83.8
3.35	81.7
2	78.9
1.18	75.4
0.6	49.4
0.425	19.6
0.3	6.3
0.212	3.4
0.15	2.3
0.063	1.2

Sample proportions	%
Cobbles	0
Gravel	21
Sand	78
Fines <0.063mm	1

Grading analysis		
D60	mm	0.8
D30	mm	0.5
D10	mm	0.3
Uniformity Coefficier	nt	2.4
Curvature Coefficien	t	0.9

Test method and date						
Testing in accordance	e with BS EN ISO 17892:					
Wet sieving method						
Reporting date:	08 Nov 16					




Sieving						
Size [mm]	% passing					
75	100					
63	100					
50	100					
37.5	100					
28	100					
20	100					
14	99.3					
10	97.7					
6.3	96.4					
5	95.8					
3.35	94.8					
2	93.8					
1.18	92.3					
0.6	88.1					
0.425	81.6					
0.3	49					
0.212	23.8					
0.15	18.1					
0.063	10.3					

Sample proportions	%
Cobbles	0
Gravel	6
Sand	84
Fines <0.063mm	10

Grading analysis		
D60	mm	0.3
D30	mm	0.2
D10	mm	
Uniformity Coefficient	t	
Curvature Coefficient		

Test method and	Test method and date					
Testing in accordan	nce with BS EN ISO 17892:					
Wet sieving method	t					
Reporting date:	08 Nov 16					





Sievir	g
Size [mm]	% passing
75	100
63	100
50	100
37.5	100
28	100
20	88.3
14	78
10	70.9
6.3	63.8
5	60.8
3.35	57.6
2	53
1.18	48.9
0.6	41.7
0.425	30.6
0.3	16.8
0.212	9.1
0.15	6.8
0.063	5.1

Sample proportions	%
Cobbles	0
Gravel	47
Sand	48
Fines <0.063mm	5

Grading analysis		
D60	mm	4.5
D30	mm	0.4
D10	mm	0.2
Uniformity Coeffici	ent	20.5
Curvature Coefficie	ent	0.2

Test method and date					
Testing in accordance	e with BS EN ISO 17892:				
Wet sieving method					
Reporting date:	08 Nov 16				



Site	Stag	Brewery	y ,							Report
Location	Lower Richmond Road, Mortlake, London SW14 7ET									No:
SUMMARY OF UNDRAINED SHEAR STRENGTH TEST RESULTS										
BH ID	Depth [m]	Moisture content [%]	Bulk density [Mg/m ³]	Dry density [Mg/m ³]	Cell pressure [kPa]	(σ ₁ -σ ₃) _f [kPa]	Failure strain [%]	Failure mode	Undrained cohesion [kPa]	Remarks
BH ID BH1		content	density	density	pressure		Failure strain	Failure	Undrained cohesion	

427

295

429

445

576

421

151

187

386

377

349

423

706

459

825

5.00

5.00

5.00

4.00

8.00

7.00

5.00

5.00

8.00

7.00

4.00

4.00

8.00

6.00

6.00

В

Ρ

В

Ρ

В

в

Ρ

Ρ

В

Ρ

В

В

В

В

В

214

148

215

223

288

211

76

94 193

189

175

212

353

230

413

1.59

1.56

1.71

1.58

1.58

1.61

1.52

1.56

1.59

1.54

1.55

1.57

1.66

1.62

1.66

2.00

1.97

2.05

2.00

1.98

2.01

1.95

1.97

1.99

1.95

1.96

1.96

2.04

2.03

2.07

190

250

310

370

430

490

100

160

220

280

340

400

460

520

590

9.55

12.55

15.55

18.55

21.55

24.55

5.05

8.05

11.50

14.05

17.05

20.05

23.05

26.05

29.55

BH2B

26

26

20

26

25

25

28

26

25

27

26

25

23

25

25

Testing in ac	cordance w	ith BS EN I	ISO 17892	UU = unco	nsolidated,	undrained	l; MUU = 1	multistage	e, unconsolio	dated, ur Date:	01 November 16
Unless stated	d otherwise	: Rate of st	train = 2mı	m/min, Sta	ndard late:	k membran	ne used w	ith thickn/	ess = 0.5m	m	
Failure mode	s: B = britt	tle, I = inte	ermediate, l	P = plastic							[Triaxial Sheet 1 of 1]



10022/OT



James Williams Soil Consultants Ltd Chiltern House Earl Howe Road Holmer Green High Wycombe Buckinghamshire HP15 6QT



QTS Environmental Ltd Unit 1

Rose Lane Industrial Estate Rose Lane Lenham Heath Kent ME17 2JN t: 01622 850410 russell.jarvis@gtsenvironmental.com

QTS Environmental Report No: 16-50918

Site Reference: Stag Brewery, Lower Richmond Road, Mortlake, London

Project / Job Ref: 10022/JW

Order No: None Supplied

Sample Receipt Date: 26/10/2016

Sample Scheduled Date: 26/10/2016

1

Report Issue Number:

Reporting Date: 01/11/2016

Authorised by:

6

Russell Jarvis Associate Director of Client Services

Authorised by:

Elyrice-yde

Ela Mysiara Inorganics & ICP Section Head





Soil Analysis Certificate						
QTS Environmental Report No: 16-50918	Date Sampled	15/10/16	15/10/16	15/10/16	15/10/16	15/10/16
Soil Consultants Ltd	Time Sampled	None Supplied				
Site Reference: Stag Brewery, Lower Richmond	TP / BH No	WS2	WS4	WS9A	WS10A	BH1
Road, Mortlake, London						
Project / Job Ref: 10022/JW	Additional Refs	None Supplied				
Order No: None Supplied	Depth (m)	2.00	4.70	3.90	4.50	1.55
Reporting Date: 01/11/2016	QTSE Sample No	235212	235213	235214	235215	235216

Determinand	Unit	RL	Accreditation					
pH	pH Units	N/a	MCERTS	8.6	7.4	7.7	8.3	8.2
Total Sulphate as SO₄	mg/kg	< 200	NONE	< 200	< 200	1002	856	206
Total Sulphate as SO ₄	%	< 0.02	NONE	< 0.02	< 0.02	0.10	0.09	0.02
W/S Sulphate as SO ₄ (2:1)	mg/l	< 10	MCERTS	23	< 10	166	161	26
W/S Sulphate as SO ₄ (2:1)	g/l	< 0.01	MCERTS	0.02	< 0.01	0.17	0.16	0.03
Total Sulphur	%	< 0.02	NONE	< 0.02	< 0.02	1.19	0.42	0.02

Analytical results are expressed on a dry weight basis where samples are assisted-dried at less than 30 °C Analysis carried out on the dried sample is corrected for the stone content Subcontracted analysis ⁽⁵⁾





Soil Analysis Certificate						
QTS Environmental Report No: 16-50918	Date Sampled	15/10/16	15/10/16	15/10/16	15/10/16	15/10/16
Soil Consultants Ltd	Time Sampled	None Supplied				
Site Reference: Stag Brewery, Lower Richmond	TP / BH No	BH1	BH1	BH2B	BH2B	BH2B
Road, Mortlake, London						
Project / Job Ref: 10022/JW	Additional Refs	None Supplied				
Order No: None Supplied	Depth (m)	6.55	12.55	17.05	23.05	29.55
Reporting Date: 01/11/2016	QTSE Sample No	235217	235218	235219	235220	235221

Determinand	Unit	RL	Accreditation					
pH	pH Units	N/a	MCERTS	8.1	8.8	9.1	8.9	9.3
Total Sulphate as SO ₄	mg/kg	< 200	NONE	971	1737	952	685	670
Total Sulphate as SO ₄	%	< 0.02	NONE	0.10	0.17	0.10	0.07	0.07
W/S Sulphate as SO ₄ (2:1)	mg/l	< 10	MCERTS	197	251	178	105	90
W/S Sulphate as SO ₄ (2:1)	g/l	< 0.01	MCERTS	0.20	0.25	0.18	0.11	0.09
Total Sulphur	%	< 0.02	NONE	0.57	2.56	0.63	0.72	0.61

Analytical results are expressed on a dry weight basis where samples are assisted-dried at less than 30 °C Analysis carried out on the dried sample is corrected for the stone content Subcontracted analysis ⁽⁵⁾





Soil Analysis Certificate - Sample Descriptions
QTS Environmental Report No: 16-50918
Soil Consultants Ltd
Site Reference: Stag Brewery, Lower Richmond Road, Mortlake, London
Project / Job Ref: 10022/JW
Order No: None Supplied
Reporting Date: 01/11/2016

QTSE Sample No	TP / BH No	Additional Refs	Depth (m)	Moisture Content (%)	Sample Matrix Description
\$ 235212	WS2	None Supplied	2.00	7.1	Light brown sand
\$ 235213	WS4	None Supplied	4.70	12.4	Light brown sand
\$ 235214	WS9A	None Supplied	3.90	21.9	Brown clay
\$ 235215	WS10A	None Supplied	4.50	21.7	Brown clay
\$ 235216	BH1	None Supplied	1.55	8.5	Light brown sandy clay with stones
\$ 235217	BH1	None Supplied	6.55	19.1	Brown clay
\$ 235218	BH1	None Supplied	12.55	16.1	Light grey clay
\$ 235219	BH2B	None Supplied	17.05	17	Brown clay
\$ 235220	BH2B	None Supplied	23.05	16.7	Brown clay
\$ 235221	BH2B	None Supplied	29.55	16.9	Brown clay

Moisture content is part of procedure E003 & is not an accredited test Insufficient Sample $^{\rm VS}$ Unsuitable Sample $^{\rm VS}$

\$ samples exceeded recommended holding times





Soil Analysis Certificate - Methodology & Miscellaneous Information
QTS Environmental Report No: 16-50918
Soil Consultants Ltd
Site Reference: Stag Brewery, Lower Richmond Road, Mortlake, London
Project / Job Ref: 10022/JW
Order No: None Supplied
Reporting Date: 01/11/2016

Matrix	Analysed On	Determinand	Brief Method Description	Method No
Soil	D	Boron - Water Soluble	Determination of water soluble boron in soil by 2:1 hot water extract followed by ICP-OES	E012
Soil	AR		Determination of BTEX by headspace GC-MS	E001
Soil	D		Determination of cations in soil by aqua-regia digestion followed by ICP-OES	E002
Soil	D	Chloride - Water Soluble (2:1)	Determination of chloride by extraction with water & analysed by ion chromatography	E009
Soil	AR	Chromium - Hexavalent	Determination of beyayalent chromium in soil by extraction in water then by acidification, addition of	E016
Soil	AR	Cyanide - Complex	Determination of complex cyanide by distillation followed by colorimetry	E015
Soil	AR		Determination of free cyanide by distillation followed by colorimetry	E015
Soil	AR	Cyanide - Total	Determination of total cyanide by distillation followed by colorimetry	E015
Soil	D	Cyclohexane Extractable Matter (CEM)	Gravimetrically determined through extraction with cyclohexane	E011
Soil	AR	Diesel Range Organics (C10 - C24)	Determination of hexane/acetone extractable hydrocarbons by GC-FID	E004
Soil	AR	Electrical Conductivity	Determination of electrical conductivity by addition of saturated calcium sulphate followed by electrometric measurement	E022
Soil	AR	Electrical Conductivity	Determination of electrical conductivity by addition of water followed by electrometric measurement	E023
Soil	D	Elemental Sulphur	Determination of elemental sulphur by solvent extraction followed by GC-MS	E020
Soil	AR		Determination of acetone/hexane extractable hydrocarbons by GC-FID	E004
Soil	AR		Determination of acetone/hexane extractable hydrocarbons by GC-FID	E004
			Determination of acetone/hexane extractable hydrocarbons by GC-FID for C8 to C40. C6 to C8 by	
Soil	AR	C12-C16, C16-C21, C21-C40)		E004
Soil	D	Fluoride - Water Soluble	Determination of Fluoride by extraction with water & analysed by ion chromatography	E009
Soil	D	FOC (Fraction Organic Carbon)	Determination of fraction of organic carbon by oxidising with potassium dichromate followed by	E010
Soil	D	Loss on Ignition @ 450oC	Determination of loss on ignition in soil by gravimetrically with the sample being ignited in a muffle furnace	E019
Soil	D	Magnesium - Water Soluble	Determination of water soluble magnesium by extraction with water followed by ICP-OES	E025
Soil	D		Determination of metals by aqua-regia digestion followed by ICP-OES	E002
Soil	AR	Mineral Oil (C10 - C40)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge	E004
Soil	AR	Moisture Content	Moisture content; determined gravimetrically	E003
Soil	D	Nitrate - Water Soluble (2:1)	Determination of nitrate by extraction with water & analysed by ion chromatography	E009
Soil	D	Organic Matter	Determination of organic matter by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	AR	PAH - Speciated (EPA 16)	Determination of PAH compounds by extraction in acetone and hexane followed by GC-MS with the use of surrogate and internal standards	E005
Soil	AR	PCB - 7 Congeners	Determination of PCB by extraction with acetone and hexane followed by GC-MS	E008
Soil	D	Petroleum Ether Extract (PEE)	Gravimetrically determined through extraction with petroleum ether	E011
Soil	AR	pH	Determination of pH by addition of water followed by electrometric measurement	E007
Soil	AR	Phenols - Total (monohydric)	Determination of phenols by distillation followed by colorimetry	E021
Soil	D	Phosphate - Water Soluble (2:1)	Determination of phosphate by extraction with water & analysed by ion chromatography	E009
Soil	D	Sulphate (as SO4) - Total	Determination of total sulphate by extraction with 10% HCl followed by ICP-OES	E013
Soil	D	Sulphate (as SO4) - Water Soluble (2:1)	Determination of sulphate by extraction with water & analysed by ion chromatography	E009
Soil	D		Determination of water soluble sulphate by extraction with water followed by ICP-OES	E014
Soil	AR		Determination of sulphide by distillation followed by colorimetry	E018
Soil	D	Sulphur - Total	Determination of total sulphur by extraction with aqua-regia followed by ICP-OES	E024
Soil	AR	SVOC	Determination of semi-volatile organic compounds by extraction in acetone and hexane followed by GC- MS	E006
Soil	AR	Thiocyanate (as SCN)	Determination of thiocyanate by extraction in caustic soda followed by acidification followed by addition of ferric nitrate followed by colorimetry	E017
Soil	D	Toluene Extractable Matter (TEM)	Gravimetrically determined through extraction with toluene	E011
Soil	D	Total Organic Carbon (TOC)	Determination of organic matter by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	AR		Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge for C8 to C35. C5 to C8 by headspace GC-MS	E004
Soil	AR	C5-C7, C7-C8, C8-C10, C10-C12, C12- C16, C16-C21, C21-C35, C35-C44)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge for C8 to C44. C5 to C8 by headspace GC-MS	E004
Soil	AR		Determination of volatile organic compounds by headspace GC-MS	E001
Soil	AR	VPH (C6-C8 & C8-C10)	Determination of hydrocarbons C6-C8 by headspace GC-MS & C8-C10 by GC-FID	E001